MILL CREEK RESIDENTIAL TRUST
CROWN VALLEY/CABOT APARTMENTS
PRECISE GRADING & DRAINAGE PLANS
LAGUNA NIGUEL, CALIFORNIA



VICINITY MAP
N.T.S.
T.G. 922-A7

GENERAL NOTES

1. ALL WORK SHALL BE IN ACCORDANCE WITH THE GRADING CODE OF THE CITY OF LAGUNA NIGUEL AND ANY SPECIAL REQUIREMENTS OF THE PERMIT. A COPY OF THE GRADING CODE AND MANUAL SHALL BE RETAINED ON THE JOB SITE WHILE WORK IS IN PROGRESS. WHEN REFERENCED ON THE PLANS, A COPY OF OC PUBLIC WORKS STANDARD PLANS SHALL ALSO BE RETAINED ON THE SITE.
2. GRADING SHALL NOT BE STARTED WITHOUT FIRST NOTIFYING THE CITY GRADING INSPECTOR, A PRE GRADING MEETING ON THE SITE IS REQUIRED BEFORE START OF GRADING WITH THE FOLLOWING PEOPLE PRESENT: OWNER, GRADING CONTRACTOR, DESIGN CIVIL ENGINEER, SOIL ENGINEER, GEOLOGIST, CITY GRADING INSPECTOR AND WHEN REQUIRED THE ARCHAEOLOGIST AND PALEONTOLOGIST. THE REQUIRED INSPECTIONS FOR GRADING WILL BE EXPLAINED AT THIS MEETING.
3. AN APPROVED COPY OF THE GRADING PLAN SHALL BE ON THE PERMITTED SITE WHILE WORK IS IN PROGRESS.
4. CUT AND FILL SLOPES SHALL BE NO STEEPER THAN 2 FOOT HORIZONTAL TO 1 FOOT VERTICAL (2:1).
5. FILLS SHALL BE COMPACTED THROUGHOUT TO A MINIMUM OF 90% RELATIVE DENSITY. AGGREGATE BASE FOR ASPHALTIC AREAS SHALL BE COMPACTED TO MINIMUM OF 95% RELATIVE DENSITY. MAXIMUM DENSITY SHALL BE DETERMINED BY CALIFORNIA BUILDING CODE STANDARD NO. 70-1 OR APPROVED EQUIVALENT, AND FIELD DENSITY BY CALIFORNIA BUILDING CODE STANDARD NO. 70-2 OR APPROVED EQUIVALENT.
6. AREAS TO RECEIVE FILL SHALL BE PROPERLY PREPARED AND APPROVED IN WRITING BY *THE SOIL ENGINEER AND THE BUILDING OFFICIAL PRIOR TO PLACING FILL.*
7. FILLS SHALL BE BENCHED INTO COMPETENT MATERIAL PER OC PUBLIC WORKS STANDARD PLAN NO. 1322.
8. ALL EXISTING FILLS SHALL BE APPROVED BY THE BUILDING OFFICIAL OR REMOVED PRIOR TO PLACING ADDITIONAL FILLS.
9. ANY EXISTING IRRIGATION LINES AND CISTERNS SHALL BE REMOVED, OR CRUSHED IN PLACE, AND APPROVED BY THE BUILDING OFFICIAL AND SOIL ENGINEER.
10. STOCKPILING OF EXCESS MATERIAL SHALL BE APPROVED BY THE BUILDING OFFICIAL PRIOR TO EXCAVATION.
11. THE DESIGN ENGINEER, AS A CONDITION OF ROUGH GRADE APPROVAL, SHALL PROVIDE BLUE TOP WITH ACCOMPANYING WITNESS STAKE, SET AT THE CENTER OF EACH PAD REFLECTING THE PAD ELEVATION FOR PRECISE PERMITS AND A BLUE TOP WITH WITNESS STAKE SET AT THE DRAINAGE SWALE HIGH POINT REFLECTING THE HIGH POINT ELEVATION FOR PRELIMINARY PERMITS.
12. ALL TRENCH BACKFILLS SHALL BE TESTED AND APPROVED BY THE SOIL ENGINEER PER THE GRADING CODE.
13. THE ENGINEERING GEOLOGIST AND SOIL ENGINEER SHALL AFTER CLEARING AND PRIOR TO THE PLACEMENT OF FILL IN CANYONS, INSPECT EACH CANYON FOR AREAS OF ADVERSE STABILITY AND TO DETERMINE THE PRESENCE OR ABSENCE OF SUBSURFACE WATER OR SPRING FLOW. IF NEEDED, SUBDRAINS WILL BE DESIGNED AND CONSTRUCTED PRIOR TO THE PLACEMENT OF FILL IN EACH RESPECTIVE CANYON.
14. SUBDRAIN OUTLETS SHALL BE COMPLETED AT THE BEGINNING OF THE SUBDRAIN CONSTRUCTION.
15. THE EXACT LOCATION OF THE SUBDRAINS SHALL BE SURVEYED IN THE FIELD FOR LINE/GRADE AND REFLECTED ON AS-GRADED PLANS.
16. ALL CUT SLOPES SHALL BE INVESTIGATED BOTH DURING AND AFTER GRADING BY THE ENGINEERING GEOLOGIST TO DETERMINE IF ANY SLOPE STABILITY PROBLEMS EXIST. SHOULD EXCAVATION DISCLOSE ANY GEOLOGICAL HAZARDS OR POTENTIAL GEOLOGICAL HAZARDS, THE ENGINEERING GEOLOGIST SHALL SUBMIT RECOMMENDED TREATMENT TO THE BUILDING OFFICIAL FOR APPROVAL.
17. WHERE SUPPORT OR BUTTRESSING OF CUT AND NATURAL SLOPES IS DETERMINED TO BE NECESSARY BY THE ENGINEERING GEOLOGIST AND SOIL ENGINEER, THE SOIL ENGINEER SHALL SUBMIT DESIGN, LOCATIONS AND CALCULATIONS TO THE BUILDING OFFICIAL PRIOR TO CONSTRUCTION. THE ENGINEERING GEOLOGIST AND SOIL ENGINEER SHALL INSPECT AND CONTROL THE CONSTRUCTION OF THE BUTTRESSING AND CERTIFY TO THE STABILITY OF THE SLOPE AND ADJACENT STRUCTURES UPON COMPLETION.
18. WHEN CUT PADS ARE BROUGHT TO NEAR GRADE, THE ENGINEERING GEOLOGIST SHALL DETERMINE IF THE BEDROCK IS EXTENSIVELY FRACTURED OR FAULTED AND WILL READILY TRANSMIT WATER. IF CONSIDERED NECESSARY BY THE ENGINEERING GEOLOGIST AND SOIL ENGINEER, A COMPACTED FILL BLANKET WILL BE PLACED.
19. THE ENGINEERING GEOLOGIST SHALL PERFORM PERIODIC INSPECTIONS AND SUBMIT A COMPLETE REPORT AND MAP UPON COMPLETION OF THE ROUGH GRADING.
20. THE COMPACTION REPORT AND APPROVAL FOR THE SOIL ENGINEER SHALL INDICATE THE TYPE OF FIELD-TESTING PERFORMED. EACH TEST SHALL BE IDENTIFIED WITH A METHOD OF OBTAINING THE IN-PLACE DENSITY, WHETHER SAND CONE OR DRIVE RING AND SHALL BE SO NOTED FOR EACH TEST. SUFFICIENT MAXIMUM DENSITY DETERMINATIONS SHALL BE PERFORMED TO VERIFY THE ACCURACY OF THE MAXIMUM DENSITY CURVES USED BY THE FIELD TECHNICIAN.
21. THE SOIL ENGINEER AND ENGINEERING GEOLOGIST SHALL PERFORM SUFFICIENT INSPECTIONS AND BE AVAILABLE DURING GRADING AND CONSTRUCTION TO VERIFY COMPLIANCE WITH THE PLANS, SPECIFICATIONS AND THE CODE WITHIN THEIR PURVIEW.
22. THE CIVIL ENGINEER SHALL BE AVAILABLE DURING GRADING TO VERIFY COMPLIANCE WITH THE PLANS, SPECIFICATIONS, CODE AND ANY SPECIAL CONDITIONS OF THE PERMIT WITHIN THE PURVIEW.
23. THE PERMITTEE IS RESPONSIBLE FOR DUST CONTROL MEASURES.
24. SANITARY FACILITIES SHALL BE MAINTAINED ON THE SITE.
25. THE LOCATION AND PROTECTION OF ALL UTILITIES IS THE RESPONSIBILITY OF THE PERMITTEE.
26. APPROVED PROTECTIVE MEASURES AND TEMPORARY DRAINAGE PROVISIONS SHALL BE USED TO PROTECT ADJOINING PROPERTIES DURING GRADING.
27. ANY EXISTING WATER WELLS SHALL BE ABANDONED IN COMPLIANCE WITH THE SPECIFICATIONS APPROVED BY COUNTY OF ORANGE, HUMAN SERVICES AGENCY, DIVISION OF ENVIRONMENTAL HEALTH.
28. *ANY EXISTING OIL WELLS SHALL BE ABANDONED IN COMPLIANCE WITH THE ORANGE* COUNTY OIL CODE TO THE APPROVAL OF OC PUBLIC WORKS/REGULATIONS SPECIAL SERVICE SECTION.
29. ANY EXISTING CESSPOOLS AND SEPTIC TANKS SHALL BE ABANDONED IN COMPLIANCE WITH THE CALIFORNIA PLUMBING CODE TO THE APPROVAL OF CITY PLANNING/BUILDING DIVISIONS, SPECIAL SERVICE SECTION.
30. PRIOR TO FINAL APPROVAL, THE CIVIL ENGINEER SHALL CERTIFY TO THE BUILDING OFFICIAL THE AMOUNT OF EARTH MOVED DURING THE GRADING OPERATION.

GENERAL NOTES CONT.

31. THE PERMITTEE SHALL COMPLY WITH THE GRADING CODE REQUIREMENTS WHEN AN EXCESS OF 5,000 CUBIC YARDS OF EACH IS TRANSPORTED TO OR FROM A PERMITTED SITE ON PUBLIC ROADWAYS.
32. ASPHALT CONCRETE SHALL BE CONSTRUCTED PER THE REQUIREMENTS OF OC PUBLIC WORKS STANDARD PLAN NO. 1805.
33. AGGREGATE BASE SECTION SHALL BE CONSTRUCTED PER OC PUBLIC WORKS STANDARD NO.1804.
34. ALL CONCRETE STRUCTURES THAT COME IN CONTACT WITH THE ON-SITE SOILS SHALL BE CONSTRUCTED WITH TYPE V CEMENT, UNLESS DEEMED UNNECESSARY BY SOLUBLE SULPHATE-CONTENT TESTS CONDUCTED BY THE SOIL ENGINEER.
35. EXPORT SOIL MUST BE TRANSPORTED TO A LEGAL DUMP OR TO A PERMITTED SITE APPROVED BY THE DISTRICT GRADING INSPECTOR.
36. SLOPES EXCEEDING 5 FEET IN HEIGHT SHALL BE PLANTED WITH APPROVED PLANT MATERIAL IN ADDITION, EXCEEDING 15 FEET IN HEIGHT SHALL BE PROVIDED WITH AN APPROVED IRRIGATION SYSTEM, UNLESS OTHERWISE APPROVED BY THE BUILDING OFFICIAL.
37. THE GRADING CONTRACTOR SHALL SUBMIT A STATEMENT OF COMPLIANCE TO THE APPROVED GRADING PLAN PRIOR TO FINAL APPROVAL.
38. ASPHALT SECTIONS MUST BE PER CODE: PARKING STALLS = 3" A/C OVER 6" A/C, DRIVES 3" A/C OVER 10" (COMM.) 12" (INDUSTRIAL), OR: PRIOR TO ROUGH GRADE *RELEASE FOR BUILDING PERMITS BY THE DISTRICT GRADING INSPECTOR, THE SOIL* ENGINEER SHALL SUBMIT FOR APPROVAL, PAVEMENT SECTION RECOMMENDATIONS BASED ON 'R' VALUE ANALYSIS OF THE SUB-GRADE SOILS, AND EXPECTED TRAFFIC INDICES.
39. PRELIMINARY SOIL AND GEOLOGY REPORTS AND ALL SUBSEQUENT REPORTS AS APPROVED BY THE CITY GRADING SECTION ARE CONSIDERED A PART OF THE APPROVED GRADING PLAN.
40. ALL EXISTING DRAINAGE COURSES THROUGH THIS SITE SHALL REMAIN OPEN UNTIL FACILITIES TO HANDLE STORM WATER ARE APPROVED AND FUNCTIONAL; HOWEVER, IN ANY CASE, THE PERMITTEE SHALL BE HELD LIABLE FOR ANY DAMAGE DUE TO OBSTRUCTING NATURAL DRAINAGE PATTERNS.
41. GRADING OPERATIONS, INCLUDING MAINTENANCE OF EQUIPMENT WITHIN ONE-HALF MILE OF A HUMAN OCCUPANCY, SHALL NOT BE CONDUCTED BETWEEN THE HOURS OF 8 P.M. AND 7 A.M. DAILY, ON SUNDAY OR ON A FEDERAL HOLIDAY.
42. ROOF GUTTERS SHALL BE INSTALLED TO PREVENT ROOF DRAINAGE FROM FALLING ON MANUFACTURED SLOPES.
43. THE PERMITTEE SHALL BE GIVEN REASONABLE NOTICE TO THE OWNER OF ADJOINING LANDS AND BUILDINGS PRIOR TO BEGINNING EXCAVATIONS WHICH MAY AFFECT THE LATERAL AND SUBJACENT SUPPORT OF THE ADJOINING PROPERTY. THE NOTICE SHALL STATE THE INTENDED DEPTH OF EXCAVATION AND WHEN THE EXCAVATION WILL COMMENCE. THE ADJOINING OWNER SHALL BE ALLOWED AT LEAST 30 DAYS AND REASONABLE ACCESS OF THE PERMITTEE PROPERTY TO PROTECT HIS STRUCTURE, IF HE SO DESIRES, UNLESS OTHERWISE PROTECTED BY LAW.

EROSION CONTROL NOTES

44. IN CASE OF EMERGENCY, CALL: GREG LUCAS WORK PHONE: 714-645-4048
45. SEDIMENTS FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON-SITE USING AN EFFECTIVE COMBINATION OF EROSION AND SEDIMENT CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE, AND STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, SIDEWALKS, GUTTERS, DRAIN INLETS OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING OR WIND.
46. ALL SEDIMENT AND CONSTRUCTION DEBRIS WHICH IS TRACKED OR DEPOSITED ONTO PUBLIC OR PRIVATE SIDEWALKS, GUTTERS OR PAVED ROADS SHALL BE REMOVED ON A DAILY BASIS BY SWEEPING OR VACUUMING AND DISPOSED OF PROPERLY. SEDIMENT AND CONSTRUCTION DEBRIS SHALL NOT BE WASHED INTO THE STORM DRAIN SYSTEM, INCLUDING THE GUTTER AND STORM DRAIN INLETS.
47. SANDBAGS, GRAVEL BAGS OR OTHER EFFECTIVE FILTER OR TRAP-TYPE BARRIERS SHALL BE USED WHERE APPROPRIATE TO INTERCEPT AND SLOW THE FLOW OF RUNOFF FROM THE CONSTRUCTION SITE AND TO TRAP SEDIMENT BEFORE IT ENTERS THE STORM DRAIN SYSTEM, INCLUDING GUTTERS AND INLETS. ALL ON-SITE STORM DRAIN INLETS SHALL BE PROTECTED AND OFF-SITE INLETS SHALL BE PROTECTED IN AREAS WHERE CONSTRUCTION ACTIVITY TRACKS SEDIMENT ON PAVED AREAS OR WHERE INLETS RECEIVE RUNOFF FROM DISTURBED AREAS.
48. EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON. NECESSARY MATERIALS SHALL BE AVAILABLE ON SITE, AND STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF TEMPORARY DEVICES WHEN RAIN IS IMMINENT.
49. EROSION CONTROL DEVICES SHALL NOT BE MOVED OR MODIFIED WITHOUT THE APPROVAL OF THE BUILDING OFFICIAL.
50. DURING THE WET SEASON, BETWEEN OCTOBER 1ST AND APRIL 30TH, EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEEDS 40%. DURING THE REMAINDER OF THE YEAR, THE EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE ONSITE AND READY FOR INSTALLATION WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEED 50% AND IN PLACE AT THE END OF EACH DAY WHEN THE 48 HOUR PROBABILITY-OF-RAIN EXCEEDS 50%.
51. AFTER A RAINSTORM ALL SILT AND DEBRIS SHALL BE REMOVED FROM STREETS, CHECK BERMS AND BASINS.
52. GRADED AREAS ON THE PERMITTED AREA PERIMETER MUST DRAIN AWAY FROM THE FACE OF SLOPES AT THE CONCLUSION OF EACH WORKING DAY. DRAINAGE TO BE DIRECTED TOWARD DE-SILTING FACILITIES.
53. ALL BARE SLOPES, INCLUDING MANUFACTURED SLOPES, SHALL BE PROVIDED WITH PROTECTIVE EROSION CONTROL MEASURES.
54. EROSION CONTROL SYSTEMS ARE DYNAMIC AND WILL CHANGE BASED ON CHANGES IN SITE DEVELOPMENT AND WEATHER CONDITIONS. THEREFORE, UPON INSPECTION, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED BY THE CITY INSPECTOR TO MINIMIZE EROSION AND SEDIMENT TRANSPORT FROM AREAS OF THE SITE *TO STREETS, SIDEWALKS, GUTTERS, DRAIN INLETS OR ADJACENT PROPERTIES.*
55. THE PERMITTEE AND CONTRACTOR SHALL BE RESPONSIBLE AND SHALL TAKE NECESSARY PRECAUTIONS TO PREVENT PUBLIC TRESPASS ONTO AREAS WHERE IMPOUNDED WATER CREATES A HAZARDOUS CONDITION.
56. THE PERMITTEE AND CONTRACTOR SHALL INSPECT THE EROSION CONTROL WORK AND ENSURE THAT THE WORK IS IN ACCORDANCE WITH THE APPROVED PLANS.

UNDERGROUND STORAGE TANK REMOVAL NOTES

57. IN THE EVENT THAT SOIL CONTAMINATION IS DISCOVERED DURING EXCAVATION AND REMOVAL OF AN EXISTING TANK, WORK SHALL BE STOPPED UNTIL A SITE ASSESSMENT AND MITIGATION PLAN HAS BEEN PREPARED, SUBMITTED AND APPROVED BY HCA/ENVIRONMENTAL HEALTH AND THE GRADING SECTION.
58. ISSUANCE OF A GRADING PERMIT DOES NOT ELIMINATE THE NEED FOR PERMITS FROM OTHER AGENCIES WITH REGULATORY RESPONSIBILITIES FOR CONSTRUCTION ACTIVITIES ASSOCIATED WITH THE WORK AUTHORIZED ON THIS PLAN.

SPECIAL NOTES

59. SURVEY MONUMENTS SHALL BE PRESERVED AND REFERENCED BEFORE CONSTRUCTION AND REPLACED AFTER CONSTRUCTION PURSUANT TO SECTION 8771 OF THE BUSINESS AND PROFESSIONAL CODE.

WATER QUALITY NOTES

60. SEDIMENTS FROM AREAS DISTURBED BY CONSTRUCTION SHALL BE RETAINED ON-SITE USING AN EFFECTIVE COMBINATION OF EROSION AND SEDIMENT CONTROLS TO THE MAXIMUM EXTENT PRACTICABLE; AND STOCKPILES OF SOIL SHALL BE PROPERLY CONTAINED TO MINIMIZE SEDIMENT TRANSPORT FROM THE SITE TO STREETS, SIDEWALKS, GUTTERS, DRAIN INLETS OR ADJACENT PROPERTIES VIA RUNOFF, VEHICLE TRACKING OR WIND.
61. ALL SEDIMENT AND CONSTRUCTION DEBRIS WHICH IS TRACKED OR DEPOSITED ONTO PUBLIC OR PRIVATE SIDEWALKS, GUTTERS OR PAVED ROADS SHALL BE REMOVED ON A DAILY BASIS BY SWEEPING OR VACUUMING AND DISPOSED OF PROPERLY. SEDIMENT AND CONSTRUCTION DEBRIS SHALL NOT BE WASHED INTO THE STORM DRAIN SYSTEM, INCLUDING THE GUTTER AND STORM DRAIN INLETS.
62. SANDBAGS, GRAVEL-BAGS OR OTHER EFFECTIVE FILTER OR TRAP-TYPE BARRIERS SHALL BE USED WHERE APPROPRIATE TO INTERCEPT AND SLOW THE FLOW OF RUNOFF FROM THE CONSTRUCTION SITE AND TO TRAP SEDIMENT BEFORE IT ENTERS THE STORM DRAIN SYSTEM, INCLUDING GUTTERS AND INLETS. ALL ON-SITE STORM DRAIN INLETS SHALL BE PROTECTED AND OFF-SITE INLETS SHALL BE PROTECTED IN AREAS WHERE CONSTRUCTION ACTIVITY TRACKS SEDIMENT ON PAVED AREAS OR WHERE INLETS RECEIVE RUNOFF FROM DISTURBED AREAS.
63. WATER AND/OR OTHER DUST PALLIATIVE AND STABILIZATION METHODS SHOULD BE USED TO PREVENT OR ALLEVIATE DUST NUISANCES (DUST CONTROL) GENERATED BY CONSTRUCTION ACTIVITIES. COVERING SMALL STOCKPILES OF SOIL AND DEBRIS OR AREAS WITH UN-STABILIZED SOIL IS AN ALTERNATIVE TO APPLYING WATER OR OTHER DUST PALLIATIVES.
64. CONSTRUCTION-RELATED MATERIALS, WASTES, SPILLS OR RESIDUES SHALL BE RETAINED ON-SITE TO MINIMIZE TRANSPORT FROM THE SITE TO STREETS, SIDEWALKS, GUTTERS, DRAIN INLETS OR ADJOINING PROPERTIES BY WIND OR RUNOFF.
65. TO PREVENT THE DISCHARGE OF POLLUTANTS FROM MATERIAL DELIVERY AND STORAGE TO THE STORM WATER SYSTEM OR WATERCOURSES, ALL MATERIALS SHALL BE PROPERLY STORED TO PREVENT SOIL CONTAMINATION AND CONTACT WITH STORM WATER RUNOFF, WHICH MAY INCLUDE APPROPRIATE COVERS, CONTAINMENT AREAS OR SURFACES AND INDOOR STORAGE.
66. STOCKPILES OF SOIL, PAVING MATERIALS, AND PRESSURE-TREATED WOOD SHALL BE MANAGED TO PREVENT AIR AND WATER POLLUTION. STOCKPILES SHOULD BE LOCATED 50 FEET AWAY FROM CONCENTRATED FLOWS OF STORM WATER, WATERCOURSES AND DRAIN INLETS. PRIOR TO THE ONSET OF PRECIPITATION, STOCKPILES SHALL BE COVERED AND PROTECTED BY A TEMPORARY PERIMETER SEDIMENT BARRIER AT ALL TIMES.
67. HAZARDOUS-MATERIAL WASTE, INCLUDING BUT NOT LIMITED TO PETROLEUM PRODUCTS, ROOFING TAR, PAINTS, SOLVENTS, STAINS, ACIDS, WOOD PRESERVATIVES, SEPTIC WASTES AND ASPHALT PRODUCTS, SHALL NOT BE ALLOWED TO ENTER THE STORM DRAIN SYSTEM OR WATERCOURSES AND SHALL BE PROPERLY TRANSPORTED, USED, STORED AND DISPOSED AS REQUIRED BY FEDERAL AND STATE LAW. PAINT BRUSHES AND EQUIPMENT FOR WATER- AND OIL-BASED PAINTS SHALL BE CLEANED WITHIN A CONTAINED AREA AND SHALL NOT BE ALLOWED TO CONTAMINATE SITE SOIL, WATERCOURSES OR STORM DRAIN SYSTEMS. WATER-BASED PAINTS SHALL BE RINSED INTO THE SANITARY SEWER SYSTEM; AND THINNERS, SOLVENTS, EXCESS OIL-BASED PAINTS AND SLUDGE SHALL BE DISPOSED AS HAZARDOUS WASTE.
68. CEMENTACEOUS PRODUCTS SUCH AS CONCRETE, MORTAR OR STUCCO FROM CONCRETE TRUCKS, POTABLE MIXERS AND MISCELLANEOUS CONTAINERS SHALL NOT BE WASHED-OUT INTO THE STORM DRAIN SYSTEM OR WATERCOURSES. DESIGNATED WASHOUT AREAS SHALL BE LOCATED AT LEAST 50 FEET FROM CONCENTRATED FLOWS OF STORM WATER, WATERCOURSES AND STORM DRAIN INLETS, AND RUNOFF FROM WASHOUT-*FREAS* SHALL BE CONTAINED BY CONSTRUCTING A TEMPORARY PIT OR BERM AREA LARGE ENOUGH TO CAPTURE THE LIQUID AND SOLID WASTE MATERIALS.
69. SAW-CUT CEMENT-CONCRETE AND ASPHALT-CONCRETE SLURRY SHALL NOT BE ALLOWED TO ENTER THE STORM DRAIN SYSTEM OR WATERCOURSES. RESIDUE FROM GRINDING OPERATIONS SHALL BE PICKED UP BY MEANS OF A VACUUM ATTACHMENT TO THE GRINDING MACHINE AND NOT ALLOWED TO FLOW ACROSS THE PAVEMENT OR BE LEFT ON THE SURFACE OF THE PAVEMENT.
70. PRIOR TO DISCHARGE OF GROUNDWATER AND ASSOCIATED WASTE, THE DISCHARGER SHALL SUBMIT AN APPLICATION TO THE SAN DIEGO REGIONAL WATER QUALITY CONTROL BOARD AND OBTAIN COVERAGE UNDER ORDER NO. R9-2008-0002, DISCHARGES FROM GROUNDWATER EXTRACTION TO SURFACE WATERS IN THE SAN DIEGO REGION EXCEPT SAN DIEGO BAY.

LEGAL DESCRIPTION

REAL PROPERTY IN THE CITY OF LAGUNA NIGUEL, COUNTY OF ORANGE, STATE OF CALIFORNIA, DESCRIBED AS FOLLOWS:

THAT PORTION OF SECTION 14, TOWNSHIP 7 SOUTH, RANGE 8 WEST OF THE SAN BERNARDINO MERIDIAN, IN THE CITY OF LAGUNA NIGUEL, COUNTY OF ORANGE, STATE OF CALIFORNIA, ACCORDING TO THE OFFICIAL PLAT OF SAID LAND IN THE DISTRICT LAND OFFICE MAY 19, 1873, DESCRIBED AS FOLLOW:

COMMENCING AT THE MOST NORTHERLY CORNER OF THE LAND DESCRIBED IN THE DEED TO LAGUNA DEVELOPMENT COMPANY, RECORDED MARCH 22, 1963, IN BOOK 6476, PAGES 877 TO 881 INCLUSIVE OF OFFICIAL RECORDS, IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY, SAID CORNER BEING A POINT ON A 1500.00 FOOT RADIUS CURVE, CONCAVE SOUTHEASTERLY A RADIAL TO SAID POINT BEARS NORTH 50°00'00" WEST; THENCE NORTHEASTERLY 505.86 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 19°19'22"; THENCE NORTH 59°19'22" EAST, 70.50 FEET TO THE BEGINNING OF A CURVE CONCAVE NORTHWESTERLY HAVING A RADIUS OF 1500.00 FEET; THENCE NORTHEASTERLY 538.54 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 20°34'14"; THENCE NORTH 38°45'08" EAST, 540.85 FEET TO THE BEGINNING OF A CURVE CONCAVE SOUTHEASTERLY HAVING A RADIUS OF 1500.00 FEET; THENCE NORTHEASTERLY 1028.08 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 39°16'11"; THENCE NORTH 78°01'19" EAST, 767.43 FEET TO THE BEGINNING OF A CURVE CONCAVE NORTHWESTERLY HAVING A RADIUS OF 1500.00 FEET; THENCE NORTHEASTERLY 305.59 FEET ALONG SAID CURVE THROUGH A CENTRAL OF 11°40'22"; THENCE NORTH 23°39'03" WEST, 52.00 FEET RADIAL TO LAST MENTIONED CURVE TO THE TRUE POINT OF BEGINNING, BEING A POINT ON A CURVE CONCAVE NORTHWESTERLY CONCENTRIC WITH LAST MENTIONED CURVE; THENCE SOUTHWESTERLY 295.00 FEET ALONG SAID CONCENTRIC CURVE THROUGH A CENTRAL ANGLE OF 11°40'22"; THENCE SOUTH 78°01'19" WEST, 78.00 FEET; THENCE NORTH 52°08'03" WEST, 41.87 FEET; THENCE NORTH 11°56'41" WEST, 178.00 FEET TO THE BEGINNING OF A CURVE CONCAVE EASTERLY HAVING A RADIUS OF 945.00 FEET; THENCE NORTHERLY 72.00 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 4°21'56"; THENCE NORTH 77°48'01" EAST, 359.07 FEET TO A POINT WHICH BEARS NORTH 20°05'55" WEST, 255.94 FEET FROM THE TRUE POINT OF BEGINNING; THENCE SOUTH 20°05'55" EAST, 255.94 FEET TO THE TRUE POINT OF BEGINNING.

APN: 636-043-03

THAT PORTION OF SECTION 14, TOWNSHIP 7 SOUTH, RANGE 8 WEST, OF THE SAN BERNARDINO MERIDIAN, IN THE COUNTY OF ORANGE, STATE OF CALIFORNIA, AS PER THE OFFICIAL PLAT OF SAID LAND FILED IN THE DISTRICT LAND OFFICE, IN THE CITY OF LAGUNA NIGUEL, COUNTY OF ORANGE, STATE OF CALIFORNIA DESCRIBED AS FOLLOWS:

COMMENCING AT THE MOST NORTHERLY CORNER OF THE LAND DESCRIBED IN THE DEED TO LAGUNA DEVELOPMENT COMPANY, RECORDED MARCH 22, 1963 IN BOOK 6476, PAGES 877 TO 881 INCLUSIVE OF OFFICIAL RECORDS, IN THE OFFICE OF THE COUNTY RECORDER OF SAID COUNTY, SAID CORNER BEING A POINT ON A 1500.00 FOOT RADIUS CURVE CONCAVE SOUTHEASTERLY A RADIAL TO SAID POINT BEARS NORTH 50°00'00" WEST, THENCE NORTHEASTERLY 505.86 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 19°19'22"; THENCE NORTH 59°19'22" EAST 70.50 FEET TO THE BEGINNING OF A CURVE, CONCAVE NORTHWESTERLY HAVING A RADIUS OF 1,500.00 FEET; THENCE NORTHEASTERLY 538.54 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 20°34'14"; THENCE NORTH 38°45'08" EAST 540.85 FEET TO THE BEGINNING OF A CURVE CONCAVE SOUTHEASTERLY HAVING A RADIUS OF 1500.00 FEET; THENCE NORTHEASTERLY 1028.08 FEET ALONG SAID CURVE, THROUGH A CENTRAL ANGLE OF 39°16'11", THENCE NORTH 78°01'19" EAST 767.43 FEET TO THE BEGINNING OF A CURVE CONCAVE NORTHEASTERLY HAVING A RADIUS OF 1500.00 FEET THENCE NORTHEASTERLY 305.59 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 11°40'22"; THENCE NORTH 23°39'03" WEST, RADIAL TO SAID LAST MENTIONED CURVE 52.00 FEET; THENCE NORTH 20°05'55" WEST 255.94 FEET TO THE TRUE POINT OF BEGINNING; THENCE NORTH 20°05'55" WEST 175.00 FEET; THENCE SOUTH 77°34'38" WEST 305.00 FEET TO A POINT ON A CURVE CONCAVE EASTERLY HAVING A RADIUS OF 945.00 FEET A RADIAL TO SAID POINT BEARS NORTH 87°00'08" WEST; THENCE SOUTHERLY 175.00 FEET ALONG SAID CURVE THROUGH A CENTRAL ANGLE OF 10°36'37" TO A POINT WHICH BEARS SOUTH 77°48'01" WEST 359.07 FEET FROM THE TRUE POINT OF BEGINNING; THENCE NORTH 77°48'01" EAST 359.07 FEET TO THE TRUE POINT OF BEGINNING.

EXCEPT THEREFROM AN UNDIVIDED TWO-THIRDS INTEREST AND TO ALL OIL, GAS AND OTHER HYDROCARBON SUBSTANCES UNDERLYING SAID LAND FOR A PERIOD OF 20 YEARS AS CONVEYED TO FIRST NATIONAL BANK IN SANTA ANA BY DEED DATED AUGUST 30, 1950 RECORDED NOVEMBER 2, 1951 IN BOOK 2249, PAGE 286, OFFICIAL RECORDS SUBJECT HOWEVER, TO THE CONDITIONS RELATING THERETO AS CONTAINED IN SAID DEED.

APN: 636-043-02

GRADING QUANTITY ESTIMATE

CUT	=	1,500 C.Y.	OVER-EXVACATION	=	0 C.Y.
FILL	=	15,000 C.Y.	EXPORT	=	0 C.Y.
NET	=	13,500 C.Y. (IMPORT)			

NOTE:
QUANTITIES SHOWN ARE ESTIMATES FOR BONDING PURPOSES ONLY. ACTUAL PAY QUANTITY CALCULATIONS ARE THE RESPONSIBILITY OF THE GRADING CONTRACTOR.

SOILS ENGINEER STATEMENT

THIS PLAN HAS BEEN REVIEWED AND CONFORMS TO RECOMMENDATIONS OF SOILS ENGINEERING/GEOLOGIC

REPORTS DATED _____. SIGNATURE AND DATE: _____.

DECLARATION OF RESPONSIBLE CHARGE

THIS GRADING PERMIT IS ISSUED SUBJECT TO THE CONDITION THAT THIS GRADING WORK SHALL BE PERFORMED UNDER THE SUPERVISION OF A CIVIL ENGINEER, REGISTERED IN THE STATE OF CALIFORNIA, AND IN COMPLIANCE WITH THE PROVISIONS OF APPENDIX CHAPTER "J" OF THE CALIFORNIA BUILDING CODE, 2010 EDITION, AS AMENDED BY THE CITY OF LAGUNA NIGUEL. UPON COMPLETION OF GRADING, PRIOR TO THE ISSUANCE OF THE BUILDING PERMITS, THE CIVIL ENGINEER SHALL SUBMIT A SIGNED CERTIFICATION TO THE DIRECTOR OF COMMUNITY DEVELOPMENT SERVICES THAT THE GRADING WORK WAS PERFORMED SUBSTANTIALLY IN ACCORDANCE WITH THESE PLANS AND, IN HIS CONSIDERED OPINION, NO CONDITION EXISTS WHICH WOULD LEAD TO INSTABILITY OF SLOPES OR TO EXCESSIVE EROSION. THE NAME OF THE CIVIL ENGINEER RESPONSIBLE FOR THE CONDITIONS UPON THE GRADING WORK PROPOSED IN THIS IS JAMES H. KAWAMURA R.C.E. NO. 30560.

I HEREBY CERTIFY THAT THESE PLANS WERE PREPARED UNDER MY SUPERVISION AND BASED UPON GEOLOGIC AND/OR SOILS INVESTIGATION.

JAMES H. KAWAMURA — 09/23/13 DATE

OWNER

MCRT INVESTMENTS LLC
949 S. COAST DRIVE
SUITE 400
COSTA MESA, CALIFORNIA 92626
ATTN.: MICHAEL GENTHE
PHONE NO.: (714) 800-1382

CIVIL ENGINEER

KHR ASSOCIATES
4100 NEWPORT PLACE DRIVE
SUITE 200
NEWPORT BEACH, CALIFORNIA 92660
ATTN.: JAMES KAWAMURA/MIKE THOMAS
PHONE NO.: (949) 756-6440

SOIL ENGINEER

GEOCON WEST, INC.
3303 N. SAN FERNANDO BLVD.
SUITE 100
BURBANK, CALIFORNIA 91504
ATTN.: GERALD KASMAN
PHONE NO.: (818) 841-1704

WDID

9 30C365973

BASIS OF BEARINGS

THE BASIS OF BEARINGS FOR THIS SUR



INDEX MAP

SCALE 1"=30'

CONSTRUCTION NOTES

		QUANTITY
1	CONSTRUCT 6-INCH HIGH PCC CURB, SEE SHEET C-4, DETAIL 1.	563 LF.
2	CONSTRUCT VARIABLE HEIGHT PCC CURB FACE, SEE SHEET C-4, DETAIL 1.	30 LF.
3	CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.	3,162 SF.
4	CONSTRUCT 6-INCH THICK PCC SLAB OVER 4-INCH THICK CRUSHED MISCELLANEOUS BASE (CMB), SEE SHEET C-4, DETAILS 4 & 5.	484 SF.
5	PROVIDE & INSTALL 80mm IMPERVIOUS CONCRETE VEHICULAR PAVERS OVER 1-INCH MIN. SAND LEVELING COARSE OVER 14-INCH CRUSH AGGREGATE BASE (CAB). SEE LANDSCAPE ARCHITECT'S PLANS FOR DETAILS, COLORS AND FINISHES.	2,855 SF.
6	CONSTRUCT 4-INCH THICK ASPHALT CONCRETE PAVEMENT OVER OVER 12-INCHES CRUSHED AGGREGATE BASE (TI=7.0) PER SOILS REPORT BY GEOCON WEST, INC. DATED 12/31/12.	7,444 SF. △1
7	CONSTRUCT 12-INCH WIDE PCC PAVER BAND. SEE SHEET C-4, DETAIL 3.	203 LF.
8	CONSTRUCT 6-INCH PCC CURB AND 24-INCH GUTTER (TYPE A2-6) PER OCPW STANDARD PLAN 120-2-0C.	24 LF.
9	CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.	1,157 LF.
10	CONSTRUCT 8-INCH CMU RAISED PLANTER WALL, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, PER SEPARATE PERMIT. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.	40 LF.
11	CONSTRUCT 8-INCH CMU RETAINING WALL, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, PER SEPARATE PERMIT. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.	210 LF.
12	CONSTRUCT PCC STAIRS AND HANDRAILS. SEE SHEET C-4, DETAIL 11.	63 LF.
13	CONSTRUCT 4-INCH THICK PCC STEP, SEE SHEET C-4, DETAIL 8.	3 EA.
14	CONSTRUCT 8-INCH WIDE PCC DEEPENED CURB (LEVEL BACKFILL COND), SEE SHEET C-4, DETAIL 6.	39 LF.
15	CONSTRUCT 8-INCH WIDE VARIABLE HEIGHT PCC GRAVITY RETAINING CURB SEE SHEET C-4, DETAIL 7.	136 LF.
16	CONSTRUCT 18-INCH WIDE PCC GUTTER AND STEEL BARRIER RAIL SEE SHEET C-4, DETAIL 9 & SHEET C-5 DETAIL 8.	434 SF.
17	CONSTRUCT 4-INCH THICK GRAVEL BED WITH 3/4" CLEAN GRAVEL SEE SHEET C-4, DETAIL 10.	595 SF.
18	CONSTRUCT 0-INCH TO 6-INCH PCC CURB FACE OVER 1-0".	45 LF.
19	ADJUST EXISTING STORM DRAIN MANHOLE OR CLEANOUT FRAME AND COVER TO FINAL FINISH GRADE.	5 EA.
20	CONSTRUCT 4-FOOT WIDE PCC LONGITUDINAL GUTTER PER OCPW *STANDARD PLAN 122-2-0C.*	21 LF. △1
21	CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.	543 LF.
22	CONSTRUCT 3-INCH THICK STABILIZED DECOMPOSED GRANITE SURFACE, COMPACT PER MANUFACTURERS SPECIFICATIONS. SUBGRADE PREPARATION PER SOILS REPORT. SEE LANDSCAPE ARCHITECT'S PLANS FOR ADDITIONAL INFORMATION.	64 LF.
23	CONSTRUCT 6-INCH PCC CURB AND 18-INCH GUTTER, SEE SHEET C-4, DETAIL 2.	175 LF.
24	CONSTRUCT TEMPORARY 24-INCH WIDE PCC GUTTER. SEE SHEET C-5, DETAIL 1.	59 LF.
25	CONSTRUCT TEMPORARY 6-INCH HIGH AC CURB PER SPPWC STANDARD PLAN 120-2, D1-8(200).	79 LF.
26	CONSTRUCT 4-INCH HIGH PCC CURB PER CALTRANS STANDARD PLAN A87A, TYPE D-4.	96 LF. △1
27	INSTALL 4" PVC (SCH. 40) IRRIGATION SLEEVE AT MIN. 18" BELOW GRADE.	50 LF.
28	INSTALL 2" PVC (SCH. 40) IRRIGATION SLEEVE AT MIN. 24" BELOW GRADE.	58 LF.
29	CONSTRUCT 4-INCH THICK ACCESSIBLE PCC RAMP, WITH #4 REBAR AT 18-INCHES O.C., SEE SHEET C-5, DETAIL 4. SEE LANDSCAPE PLANS FOR PCC COLORS AND FINISHES.	123 SF.
30	CONSTRUCT 10-INCH WIDE DEEPENED PCC SIDEWALK FOOTING SEE SHEET C-5, DETAIL 2.	25 LF. △2

STORM DRAIN NOTES

		QUANTITY
30	PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.	800 LF.
31	PROVIDE AND INSTALL 6-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.	55 LF. △
32	PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.	188 LF.
33	PROVIDE AND INSTALL 10-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.	268 LF.
34	PROVIDE AND INSTALL 12-INCH HDPE DRAINAGE PIPE. SEE SHEET C-22, DETAIL 2 FOR PIPE BEDDING.	126 LF.
35	PROVIDE AND INSTALL 18-INCH HDPE DRAINAGE PIPE. SEE SHEET C-22, DETAIL 2 FOR PIPE BEDDING.	16 LF.
36	PROVIDE AND INSTALL PVC STORM DRAIN CLEANOUT. SEE SHEET C-22, DETAILS 4 OR 8.	6 EA.
37	PROVIDE AND INSTALL 9-INCH x 9-INCH LOW PROFILE ADAPTER (NDS #930) USE 9-INCH SQUARE GRATE IN GRASS AREA (NDS #990 "GREEN"). USE 9-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #981 "BLACK"). SEE SHEET C-22, DETAIL 10.	9 EA.
38	PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.	26 EA.
39	PROVIDE AND INSTALL 6-INCH ROUND ATRIUM GRATE (NDS #90) IN SOIL AREAS AND 6-INCH ROUND GRATE (NDS #50) IN GRASS AREAS. SEE SHEET C-22, DETAIL 10.	2 EA.
40	CONSTRUCT 12-INCH WIDE ACO TRENCH DRAIN MODEL SK3-01 WITH DUCTILE IRON GRATE (H-20 LOADING). SEE SHEET C-22, DETAIL 11.	20 LF.
41	PROVIDE AND INSTALL ECCENTRIC REDUCER, SIZE PER PLAN.	8 EA.
42	PROVIDE AND INSTALL HDPE WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL. SEE SHEET C-23, DETAIL 4.	29 EA.
43	PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.	7 EA.
44	PROVIDE AND INSTALL 30° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.	11 EA.
45	PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).	6 EA.
46	REMOVE CONFLICTING PORTION OF THE EXISTING 10-INCH STORM DRAIN LINE, CONNECT PROPOSED STORM DRAIN LINE AS REQUIRED.	2 EA.
47	PROVIDE AND INSTALL 4'x6' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.	2 EA.
48	PROVIDE AND INSTALL 8'x12' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.	2 EA.
49	*PROVIDE AND INSTALL 24-INCH x 24-INCH CAST-IN-PLACE CONCRETE* DROP INLET WITH GALVANIZED STEEL GRATE AND FRAME. SEE SHEET C-23, DETAIL 1.	3 EA.
50	PROVIDE STENCILING AT CATCH BASIN AND INLETS TO DISCOURAGE ILLEGAL DUMPING OF POLLUTANTS, SEE SHEET 22, DETAIL 7.	4 EA.
51	PROVIDE AND INSTALL 4-INCH ROUND ADA COMPLIANT CHROME GRATE WITH PVC COLLAR (NDS #917SC).	2 EA.
52	CONNECT TO EXIST STORM DRAIN PIPE. CUT-IN A WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL, SEE SHEET C-23 DETAIL 4.	18 EA.
53	REMOVE ROUGH GRADING DRAINAGE BASIN, REPLACE WITH NEW 10-INCH PVC (SDR-35) DRAINAGE PIPE, WYE & BEDDING. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.	1 EA.
54	CONSTRUCT 6-INCH WIDE ACO TRENCH DRAIN MODEL KS100S (K010 NEUTRAL CHANNEL DEPTH=6.96") ADA COMPLIENT GRATE AND H-20 LOADING, SEE SHEET C-22, DETAIL 12.	43 LF.
55	PROVIDE AND INSTALL 6-INCH PERFORATED PVC (SCH 40) DRAINAGE PIPE SEE SHEET C-5, DETAIL 6.	20 LF.
56	REMOVE EXISTING 8-INCH STORM DRAIN LINE AND RISER AT PIPE FITTING.	25 LF.
57	PROVIDE AND INSTALL 18-INCH x 18-INCH LOW PROFILE ADAPTER (NDS #1830) USE 18-INCH SQUARE GRATE IN GRASS AREA (NDS #1812 "GREEN"). USE 18-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1881 "BLACK"). SEE SHEET C-22, DETAIL 10.	3 EA.
58	CONSTRUCT 4-INCH WIDE PRE-SLOPED ACO (KS100S) TRENCH DRAIN W/ ADA "HEEL RESISTANT" STAINLESS STEEL GRATE AND FRAME. SEE SHEET C-22, DETAIL 15.	1 EA.
59	CONSTRUCT 4-INCH WIDE PRE-SLOPED ACO (KS100S) TRENCH DRAIN, ADJACENT TO STAIRS, W/ ADA "HEEL RESISTANT" STAINLESS STEEL GRATE AND FRAME. SEE SHEET C-4, DETAIL 11.	3 EA.
60	CONSTRUCT CURBSIDE GRATING CATCH BASIN PER S.P.P.W.C. STANDARD PLAN NO. 303-3. CONSTRUCT 8-INCH THICK PCC LOCAL DEPRESSION, SEE SHEET C-23, DETAIL 8 OR 10.	1 EA.
61	CONSTRUCT CURB OPENING CATCH BASIN PER S.P.P.W.C. STANDARD PLAN NO. 300-3. CONSTRUCT 8-INCH THICK PCC LOCAL DEPRESSION, SEE SHEET C-23, DETAIL 9 OR 10.	2 EA.
62	INSTALL 8-INCH DIAMETER NYLOPLAST DRAINAGE BASIN WITH ATRIUM GRATE. SEE SHEET C-5, DETAIL 1.	1 EA.

ABBREVIATIONS

AB	AGGREGATE BASE
AC	ASPHALT CONCRETE
AR	AIR RELEASE VALVE ASSEMBLY
B	BOLLARD
BFD	BACKFLOW DEVICE
BO	WATER LINE BLOW-OFF
BW	BACK OF WALK
BOP	BOTTOM OF PIPE
BOS	BOTTOM OF STAIRS
BOT	BOTTOM
CATV	CABLE TELEVISION
CB	CATCH BASIN
CL	CENTERLINE
CMU	CONCRETE MASONRY UNIT
COMM	UNDERGROUND COMMUNICATION LINES
DCDA	DOUBLE CHECK DETECTOR ASSEMBLY
DI	DRAINAGE INLET
DIP	DUCTILE IRON PIPE
DS	DOWN SPOUT
DWY	DRIVEWAY
EG	EDGE OF GUTTER
ELEC	UNDERGROUND ELECTRICAL LINES
ELEC-OH	OVERHEAD ELECTRICAL LINES
EMH	ELECTRICAL MANHOLE
EP	EDGE OF PAVEMENT
EG	EDGE OF GUTTER
EX.	EXISTING
FG	FINISHED GRADE
FDC	FIRE DEPARTMENT CONNECTION
FH	FIRE HYDRANT
FL	FLOW LINE
FS	FINISHED SURFACE
G	GAS
GB	GRADE BREAK
GM	GAS METER
GV	GAS VALVE
HP	HIGH POINT
INV	INVERT
IRR	IRRIGATION
LG	LIP OF GUTTER
LP	LOW POINT
LS	LIGHT STANDARD
NG	NATURAL GRADE
PA	PLANTER AREA
PB	PULL BOX
PCC	PORTLAND CEMENT CONCRETE
PED	ABOVE GROUND UTILITY PEDESTAL
PIV	POST INDICATOR VALVE
PL	PROPERTY LINE
PVC	POLYVINYL CHLORIDE PIPE
RD	ROOF DRAIN
RW	RIGHT OF WAY
S	SEWER LINES
SCO	SEWER CLEANOUT
SD	STORM DRAIN
SDMH	STORM DRAIN MANHOLE
SL	STREET LIGHT
SMH	SEWER MANHOLE
SW	SIDEWALK
TELE	UNDERGROUND TELEPHONE LINES
TMH	TELEPHONE MANHOLE
TC	TOP OF CURB
TF	TOP OF FOOTING
TG	TOP OF GRATE
TP	TOP OF PIPE
TS	TRAFFIC SIGNAL EQUIPMENT
TW	TOP OF WALL
WM	WATER METER
WV	WATER VALVE

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; ADDED CONSTRUCTION NOTES & REVISED	
		QUANTITIES; REVISED INDEX MAP TO SHOW NEW SHEETS.	
2	1/16/15	CHANGED CONST. NOTE 30	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration: 03/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **INDEX MAP, CONST. NOTES & QUANTITIES**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-2**

G:\JOBS\JOBS - Laguna Niguel\023\Precise Grading\MODEL-PG-02-INDEX.dwg May 1, 2015 - 11:54am Jose



LEGEND:

LIMITS OF GRADING/DAYLIGHT LINE

0 10 20 40 80

SCALE: 1"=20'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration 03/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION:
EXCAVATION PLAN

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-3

R:\MGR\WORK\Laguna Niguel\CD\Precise Grading\MDS\A-PG-03-EXCV.dwg May 11, 2015 - 11:56am Jose



SCALE: NONE

STABILIZED EARTHEN SWALE | 13



SCALE: NONE

PCC RETAINING WALL GUTTER AND BARRIER RAIL | 9



NOTE:
TOOLED CONTROL JOINTS SHALL BE PLACED EVERY 4'-0" O.C. MAX. CONTROL JOINTS SHALL BE PLACED EVERY 8'-0" O.C. MAX. EXPANSION JOINTS SHALL BE PLACED AT 24'-0" O.C. MAX.

SCALE: NONE

CONCRETE JOINT DETAILS | 5



NOTE:
CONTROL JOINTS SHALL BE PLACED EVERY 8'-0" O.C. MAX. & AT EVERY B.C. & E.C.

SCALE: NONE

6" PCC CURB AT AC PAVEMENT | 1

GENERAL NOTES:

* STRENGTH OF CONCRETE AND CEMENT TYPE FROM ALL CONCRETE IN CONTACT WITH SOIL TO BE DETERMINED BY THE PROJECT SOIL ENGINEER IN THE FIELD BASED ON SULFATE CONTENT OF THE SOIL.



SCALE: NONE

GRAVEL BED DETAIL | 10



NOTE:
CONTROL JOINTS SHALL BE PLACED EVERY 8'-0" O.C. MAX. & AT EVERY B.C. & E.C.

SCALE: NONE

8" WIDE DEEPENED PCC CURB | 6



NOTES:

1. PROVIDE CONTROL JOINTS AT 10'-0" O.C. (15'-0" MAX.) AND AT EVERY BC AND EC; EXPANSION JOINTS AT 30'-0" O.C.
2. MAX. 5.0% CROSS SLOPE WITHIN GUTTER WHEN AN ACCESSIBLE PATH OF TRAVEL INTERSECTS THE CURB & GUTTER OR RIBBON GUTTER, EXTEND THE WARPED GUTTER 1.0' BEYOND EITHER SIDE OF THE ACCESSIBLE PATH OF TRAVEL AND TRANSITION BACK TO STANDARD GUTTER.

SCALE: NONE

6" PCC CURB WITH 18" WIDE GUTTER | 2



CONC. STAIR WITH TRENCH DRAIN OPTION



NOSING ENLARGEMENT



SECTION "A"-"A"



CONC. STAIR/RAIL SUPPORT SECTION

LEGEND:

1. CONCRETE STEPS (520-C-2500)*
2. SEE NOSING ENLARGEMENT DETAIL
3. 1/2" RADIUS CONTINUOUS
4. FINISH SURFACE
5. 1/4" X 1/4" GROOVING PER CBC CODE (SLIP RESISTANT WITH CONTRASTING COLOR, TYPICAL AT ALL NOSING)
6. 1-1/2" DIA. ROUND PAINTED STEEL HANDRAIL, COORDINATE STYLE AND COLOR WITH THE ARCHITECT & LANDSCAPE ARCHITECT.
7. 1-1/2" DIA. ROUND PAINTED STEEL POST, COORDINATE WITH LANDSCAPE ARCHITECT, BLOCK OUT 2" DIA. x 8-1/2" DEEP SQUARE
8. BLOCK OUT 2" DIA. x 8-1/2" DEEP POST OPENING, PRIOR TO POURING CONCRETE, FILL W/ NON-SHRINK GROUT AFTER POST IS PLACED, ALIGNED AND LEVELED.
9. 1/2" EXPANSION JOINT W/ BACKER ROD, FILLER & SEALANT PROVIDE 1/2" TOOLED RADIUS.
10. 1/2" DIA. x 12" LONG. SMOOTH STEEL ROD 24" O.C. GREASE ONE END AND PROVIDE EXPANSION CAP ON OTHER END. 11. #4 REBAR AT 18" O.C. BOTH WAYS
11. #4 REBAR CONTINUOUS NOSING BAR
12. #4 REBAR AT 18" O.C. BOTH WAYS
13. #4 REBAR CONTINUOUS
14. #4 TIE BAR AT 18" O.C.
15. FINISH GRADE WHERE OCCURS
16. #4 REBAR TOP AND BOTTOM, #4 MID BAR AT WALL OVER 12" TOTAL HEIGHT.
17. #4 VERTICAL AT 18" O.C.
18. CONCRETE CHEEK WALL AS REQUIRED (520-C-2500)*

SCALE: NONE

TYPICAL CONCRETE STAIRS DETAIL (PER SEPARATE BUILDING PERMIT, SHOWN FOR REFERENCE ONLY) | 11



NOTE:

1. EXPANSION JOINTS SHALL EXTEND THROUGH THE ENTIRE CURB AND BE SPACED AT A MAXIMUM DISTANCE OF 40.0'. EXPANSION JOINT TO BE PRE-MOLDED FILLER WITH CAULKING SEALANT ON EARTHEN SIDE.

SCALE: NONE

PCC GRAVITY RETAINING CURB | 7



SCALE: NONE

PCC PAVER BAND DETAIL | 3



NOSE DETAIL



SCALE: NONE

CONCRETE STEP DETAIL | 8



SCALE: NONE

CONCRETE SECTIONS | 4

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA — Expiration 06/30/16

SHEET DESCRIPTION:
SITE DETAILS

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-4

R:\WORK\WORK-Laguna Niguel\G13\Precise Grading\WORK-In-PG-04-15.dwg May 11, 2015 - 11:38am Jose



LEGEND:

1. CONCRETE (569-C-2500) ACCESSIBLE RAMP #4 REBAR AT 18" O.C. W/MEDIUM BROOM FINISH TO RUN PERPENDICULAR TO SIDEWALK.
2. 1 1/2" O.D. PAINTED STEEL HANDRAIL PER MINIMUM CBC REQUIREMENTS. FOR PROJECT SPECIFIC DECORATIVE RAILING, SEE LANDSCAPING PLANS.
3. 1 1/2" O.D. PAINTED STEEL POST PER MINIMUM CBC REQUIREMENTS. FOR PROJECT SPECIFIC DECORATIVE POST, SEE LANDSCAPING PLANS.
4. 1 1/2" O.D. PAINTED STEEL GUIDE RAIL PER MINIMUM CBC REQUIREMENTS. FOR PROJECT SPECIFIC DECORATIVE RAIL, SEE LANDSCAPING PLANS. SEE LANDSCAPING PLANS FOR RAIL COLOR.
5. BLOCK OUT 2 1/2" x 2 1/2" x 8 1/2" DEEP SQ. POST OPENING PRIOR TO POURING CONCRETE, FILL W/ NON-SHRINK GROUT AFTER POST IS PLACED, ALIGNED AND LEVELED, OR CORE DRILL 2 1/2" DIA. x 8 1/2" DEEP HOLE AND FILL WITH NON-SHRINK GROUT AFTER POST IS PLACED, ALIGNED AND LEVELED.



SCALE: NONE

TYPICAL CONCRETE ACCESSIBLE RAMP DETAIL 4



INTERMEDIATE GUTTER INLET



SECTION "A"-"A"



SECTION "B"-"B" AT INLET

SCALE: NONE

2-FOOT WIDE CONCRETE BROW DITCH & FLOWLINE TRANSITION DETAILS AT INLET LOCATION 1



SECTION "A"-"A"



SECTION "B"-"B" AT INLET



SECTION "C"-"C"



END CONDITION GUTTER INLET



INTERMEDIATE GUTTER INLET



SCALE: NONE

18-INCH WIDE CONCRETE BROW DITCH & FLOWLINE TRANSITION DETAILS AT INLET LOCATIONS 8

10" WIDE DEEPENED PCC SIDEWALK FOOTING 2

GENERAL NOTES:

* STRENGTH OF CONCRETE AND CEMENT TYPE FROM ALL CONCRETE IN CONTACT WITH SOIL TO BE DETERMINED BY THE PROJECT SOIL ENGINEER IN THE FIELD BASED ON SULFATE CONTENT OF THE SOIL.

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REMOVED ORIGINAL DETAILS 1, 2, 3, 4 & 6; ADDED NEW DETAIL 1 & 4;	
		CHANGED PROJECT ADDRESS.	
2	1/16/15	ADDED DETAIL 2	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration date: 09/30/15 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **SITE DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-5

© KHR ASSOCIATES

K:\ACTIVE\26001-Laguna Ridge\CAD\Precise Grading\MCSLA-PG-05-2.dwg May 11, 2015 - 11:59am jose



SECTION "A"-"A"

SCALE: 1"=4'



SECTION "D"-"D"

SCALE: 1"=4'



SECTION "B"-"B"

SCALE: 1"=4'



SECTION "E"-"E"

SCALE: 1"=4'





SECTION "C"-"C"

SCALE: 1"=4'



SECTION "F"-"F"

SCALE: 1"=4'



SECTION "G"-"G"

SCALE: 1"=4'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNITY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED DECOMPOSED GRANITE SURFACE ALONG SOUTHERLY PATH; REVISED PROJECT ADDRESS; REVISED SECTION "A"-"A"; UPDATED OFF-SITE PORTION OF SECTION "E-E"; LOWERED FIP BOX AND SD INVERTS.	
2	1/16/15	REVISED SECTION "A"-"A"	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration: 03/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION: **SITE SECTIONS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-6**

R:\WORK\5376001-Laguna Niguel\03\Precise Grading\5376DL-PG-08-SEC.dwg May 11, 2015 - 12:02pm Jose



SECTION "L"-"L"
SCALE: 1"=4'



SECTION "H"-"H"
SCALE: 1"=4'



SECTION "M"-"M"
SCALE: 1"=4'



SECTION "J"-"J"
SCALE: 1"=4'



SECTION "K"-"K"
SCALE: 1"=4'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED DECOMPOSED GRANITE SURFACE ALONG SOUTHERLY PATH, REVISED SECTION "H-H", "J-J" & "L-L"; REVISED PROJECT ADDRESS; ADDED SECT. "M-M"	
2	1/16/15	REVISED SECTION "H"-"H" & "J"-"J"	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration: 03/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **SITE SECTIONS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-7**

R:\WORK\CROWN-Laguna Niguel\CIVIL\Precise Grading\MCBUA-PRC-07-SEC.dwg May 11, 2015 - 12:54pm Jose



CONSTRUCTION NOTES

1. CONSTRUCT 6-INCH HIGH PCC CURB, SEE SHEET C-4, DETAIL 1.
3. CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.
5. PROVIDE & INSTALL 80mm IMPERVIOUS CONCRETE VEHICULAR PAVERS. OVER 1-INCH MIN. SAND LEVELING COARSE OVER 14-INCH CRUSH AGGREGATE BASE (CAB), SEE LANDSCAPE ARCHITECT'S PLANS FOR DETAILS, COLORS AND FINISHES.
6. CONSTRUCT 4-INCH THICK ASPHALT CONCRETE PAVEMENT OVER OVER 12-INCHES CRUSHED AGGREGATE BASE (TI=7.0) PER SOILS REPORT BY GEOCON WEST, INC. DATED 12/31/12.
7. CONSTRUCT 12-INCH WIDE PCC PAVER BAND. SEE SHEET C-4, DETAIL 3.
8. CONSTRUCT 6-INCH PCC CURB AND 24-INCH GUTTER (TYPE A2-6) PER OCPW STANDARD PLAN 120-2-0C.
20. CONSTRUCT 4-FOOT WIDE PCC LONGITUDINAL GUTTER PER OCPW STANDARD PLAN 122-2-0C.
21. CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.
23. CONSTRUCT 6-INCH PCC CURB AND 18-INCH GUTTER, SEE SHEET C-4, DETAIL 2.
24. CONSTRUCT TEMPORARY 24-INCH WIDE PCC GUTTER. SEE SHEET C-5, DETAIL 1.
25. CONSTRUCT TEMPORARY 6-INCH HIGH AC CURB PER SPPWC STANDARD PLAN 120-2, D1-8(200).
26. CONSTRUCT 4-INCH HIGH PCC CURB PER CALTRANS STANDARD PLAN A87A, TYPE D-4.
27. INSTALL 4" PVC (SCH. 40) IRRIGATION SLEEVE AT MIN. 18" BELOW GRADE.
28. INSTALL 2" PVC (SCH. 40) IRRIGATION SLEEVE AT MIN. 24" BELOW GRADE.

DEMOLITION NOTES

19. REMOVE AND DISPOSE OF EXISTING CONCRETE GUTTER.

LEGEND

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE
- (HIDDEN)
- NEW CONCRETE PAVEMENT
- NEW ASPHALT PAVEMENT
- NEW 80mm PERVIOUS CONCRETE PAVERS, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR & FINISH
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT
- RIGHT-OF-WAY/PROPERTY LINE

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).
3. PROPOSED IMPROVEMENT ON ADJACENT PROPERTY TO THE NORTH (PICERNE SITE) IS AN INTERIM CONDITION ONLY.

0 5 10 20 30
SCALE: 1"=10'

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED SHEET TO SHOW THE NEW DWY. & TEMP. 1.8:1 CUT SLOPE;	
		CHANGED SITE ADDRESS; ADDED SITE SECTION "H-H"	
2	1/16/15	REVISED TRANSFORMER ENCLOSURE, RETAINING WALL ALIGNMENT AND LOAD	
		ZONE AREA	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA — Expires 6/30/16

SHEET DESCRIPTION: **PRECISE GRADING PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER: 5376001

SHEET NO.: C-8

R:\MCP\MCP1-Irvine Ngun\101\Precise Grading\MCP1A-PG-08.dwg May 11, 2015 - 12:20pm Jose



CONSTRUCTION NOTES

1. CONSTRUCT 6-INCH HIGH PCC CURB, SEE SHEET C-4, DETAIL 1.
3. CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.
4. CONSTRUCT 6-INCH THICK PCC SLAB OVER 4-INCH THICK CRUSHED MISCELLANEOUS BASE (CMB), SEE SHEET C-4, DETAILS 4 & 5. △1
5. PROVIDE & INSTALL 80mm IMPERVIOUS CONCRETE VEHICULAR PAVERS OVER 1-INCH MIN. SAND LEVELING COARSE OVER 14-INCH CRUSH AGGREGATE BASE (CAB), SEE LANDSCAPE ARCHITECT'S PLANS FOR DETAILS, COLORS AND FINISHES.
6. CONSTRUCT 4-INCH THICK ASPHALT CONCRETE PAVEMENT OVER OVER 12-INCHES CRUSHED AGGREGATE BASE (TI=7.0) PER SOILS REPORT BY GEOCON WEST, INC. DATED 12/31/12.
7. CONSTRUCT 12-INCH WIDE PCC PAVER BAND. SEE SHEET C-4, DETAIL 3. △1
15. CONSTRUCT 8-INCH WIDE VARIABLE HEIGHT PCC GRAVITY RETAINING CURB SEE SHEET C-4, DETAIL 7. △2
23. CONSTRUCT 6-INCH PCC CURB AND 18-INCH GUTTER, SEE SHEET C-4, DETAIL 2.

LEGEND:

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE (HIDDEN)
- NEW CONCRETE PAVEMENT
- NEW ASPHALT PAVEMENT
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED SHEET TO SHOW THE NEW DWY.; REVISED DRIVE AISLE DRAINAGE	
2	1/16/15	REVISED ROADWAY ALIGNMENT; DELETED DOG PARK; REMOVED NOTE 14	
		ADDED NOTE 15	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expires 03/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION: **PRECISE GRADING PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER: 5376001

SHEET NO.: C-9 △

K:\MDP\WDP-Layout Xrpwn\C9\Precise Grading\MDBLN-PG-09.dwg May 11, 2015 - 12:07pm Alex



CONSTRUCTION NOTES

(9) CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.

(17) CONSTRUCT 4-INCH THICK GRAVEL BED WITH 3/4" CLEAN GRAVEL SEE SHEET C-4, DETAIL 10.

(21) CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.

LEGEND

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE
- (HIDDEN)
- NEW CONCRETE PAVEMENT
- *NEW ASPHALT PAVEMENT*
- NEW 80mm PERVIOUS CONCRETE PAVERS, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR & FINISH
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

0 5 10 20 30
SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **PRECISE GRADING PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA
PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-10** △

R:\CAD\PLAN\P-Laguna Niguel\CDD\Precise Grading\MCDLN-PG-10.dwg May 11, 2015 - 12:09pm Jose

CONSTRUCTION NOTES

(3) CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.

LEGEND:

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE
- (HIDDEN)
- NEW CONCRETE PAVEMENT
- NEW ASPHALT PAVEMENT
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

0 5 10 20 30
SCALE: 1"=10'

Know what's Below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	LOWERED TOP OF GRATE ELEVATION ON FTP, ADDED INLET AND ADJUSTED SWALE LINES; REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY; ADD SITE SECTION "M-M"	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION:
PRECISE GRADING PLAN

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-11 △

S:\WORK\JACR-Haboro Signed\CDS\Precise Grading\JACR-PG-11.dwg May 13, 2015 - 12:10pm jose



CONSTRUCTION NOTES

3. CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.
9. CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.
10. CONSTRUCT 8-INCH CMU RAISED PLANTER WALL, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, PER SEPARATE PERMIT. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.
14. CONSTRUCT 8-INCH WIDE PCC DEEPENED CURB (LEVEL BACKFILL COND), SEE SHEET C-4, DETAIL 6.
15. CONSTRUCT 8-INCH WIDE VARIABLE HEIGHT PCC GRAVITY RETAINING CURB SEE SHEET C-4, DETAIL 7.
16. CONSTRUCT 18-INCH WIDE PCC GUTTER AND STEEL BARRIER RAIL SEE SHEET C-4, DETAIL 9 & SHEET C-5 DETAIL 8.
21. CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.
22. CONSTRUCT 3-INCH THICK STABILIZED DECOMPOSED GRANITE SURFACE, COMPACT PER MANUFACTURERS SPECIFICATIONS. SUBGRADE PREPARATION PER SOILS REPORT. SEE LANDSCAPE ARCHITECT'S PLANS FOR ADDITIONAL INFORMATION.

LEGEND:

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE
- NEW CONCRETE PAVEMENT
- NEW DECOMPOSE GRANITE
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT
- PROPOSED CONCRETE DRAINAGE DITCH

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

0 5 10 20 30
SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADD RETAINING CURB & WALL, REVISED GRADES & INLET LOC. PER FINAL ST. IMPRV. PLANS; ADDED DECOMPOSED GRANITE SURFACE ALONG SOUTHERLY PATH, MOVED INLET AWAY FROM BLDG. TO AVOID FOOTING CONFLIT; REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **PRECISE GRADING PLAN**

CROWN CABOT LUXURY APARTMENTS △
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA
PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-12** △

F:\WORK\WORK-Laguna Niguel\GRD\Precise Grading\WORK-PG-12.dwg May 11, 2015 - 12:11pm Jose



CONSTRUCTION NOTES

(9) CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.

(16) CONSTRUCT 18-INCH WIDE PCC GUTTER AND STEEL BARRIER RAIL SEE SHEET C-4, DETAIL 9 & SHEET C-5 DETAIL B.

⚠1 (22) CONSTRUCT 3-INCH THICK STABILIZED DECOMPOSED GRANITE SURFACE, COMPACT PER MANUFACTURERS SPECIFICATIONS. SUBGRADE PREPARATION PER SOILS REPORT. SEE LANDSCAPE ARCHITECT'S PLANS FOR ADDITIONAL INFORMATION.

LEGEND:

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE
- (HIDDEN)
- NEW CONCRETE PAVEMENT
- ⚠1 NEW DECOMPOSE GRANITE
- DIRECTION OF SURFACE FLOW. SURFACE SHALL SLOPE AWAY FROM BUILDING AND SITE WALLS AT 2.0% MINIMUM.
- LIMITS OF PRECISE GRADING PERMIT
- PROPOSED CONCRETE DRAINAGE DITCH

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

N

0 5 10 20 30

SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADJUSTED FTP WALL LOCATION & SIZE, ADJUSTED FILTERRA LOCATION &	
		TOP OF GRATE, ADJUSTED INLET LOCATION TO AVOID BLDG. FOOTING	
		CONFLICTS; ADDED DECOMPOSED GRANITE SURFACE ALONG SOUTHERLY PATH;	
		REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW	
		DRIVEWAY	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)
REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 12/31/15 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **PRECISE GRADING PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠1
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-13** ⚠1

N:\AUTOPROJECT-Laguna Niguel\CAD\Precise Grading\MODULA-SP-13.dwg May 13, 2015 - 12:13pm Jose



GENERAL NOTE:
1. BUILDING/PODIUM DRAINAGE AND DESIGN PER SEPARATE PLAN AND PERMIT.

SCALE: 1"=8'

GRADING DETAIL - CABOT ROAD MAIN ENTRANCE 6



SCALE: 1"=4'

GRADING DETAIL - TRANSFORMER ENCLOSURE/STAIRS AT LOAD ZONE 8



SCALE: 1"=4'

GRADING DETAIL - AT MONUMENT SIGN 1



SCALE: 1"=4'

GRADING DETAIL - LEVEL B2 STAIR EXIT 2



SCALE: 1"=4'

GRADING DETAIL - CABOT ROAD BLDG. EXIT 5

CONSTRUCTION NOTES

1. CONSTRUCT 6-INCH HIGH PCC CURB, SEE SHEET C-4, DETAIL 1.
2. CONSTRUCT VARIABLE HEIGHT PCC CURB FACE, SEE SHEET C-4, DETAIL 1.
3. CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.
4. CONSTRUCT 6-INCH THICK PCC SLAB OVER 4-INCH THICK CRUSHED MISCELLANEOUS BASE (CMB), SEE SHEET C-4, DETAILS 4 & 5.
5. PROVIDE & INSTALL 80mm IMPERVIOUS CONCRETE VEHICULAR PAVERS OVER 1-INCH MIN. SAND LEVELING COARSE OVER 14-INCH CRUSH AGGREGATE BASE (CAB), SEE LANDSCAPE ARCHITECT'S PLANS FOR DETAILS, COLORS AND FINISHES.
6. CONSTRUCT 4-INCH THICK ASPHALT CONCRETE PAVEMENT OVER OVER 12-INCHES CRUSHED AGGREGATE BASE (TI=7.0) PER SOILS REPORT BY GEOCON WEST, INC. DATED 12/31/12.
9. CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.
11. CONSTRUCT 8-INCH CMU RETAINING WALL, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, PER SEPARATE PERMIT. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.
12. CONSTRUCT PCC STAIRS AND HANDRAILS. SEE SHEET C-4, DETAIL 11.
14. CONSTRUCT 8-INCH WIDE PCC DEEPENED CURB (LEVEL BACKFILL COND), SEE SHEET C-4, DETAIL 6.
15. CONSTRUCT 8-INCH WIDE VARIABLE HEIGHT PCC GRAVITY RETAINING CURB SEE SHEET C-4, DETAIL 7.
18. CONSTRUCT 0-INCH TO 6-INCH PCC CURB FACE OVER 1-0'.
21. CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.
22. CONSTRUCT 3-INCH THICK STABILIZED DECOMPOSED GRANITE SURFACE, COMPACT PER MANUFACTURER'S SPECIFICATIONS. SUBGRADE PREPARATION PER SOILS REPORT. SEE LANDSCAPE ARCHITECT'S PLANS FOR ADDITIONAL INFORMATION.
29. CONSTRUCT 4-INCH THICK ACCESSIBLE PCC RAMP. WITH #4 REBAR AT 18-INCHES O.C., SEE SHEET C-5, DETAIL 4. SEE LANDSCAPE PLANS FOR PCC COLORS AND FINISHES.
30. CONSTRUCT 10-INCH WIDE DEEPENED PCC SIDEWALK FOOTING SEE SHEET C-5, DETAIL 2.

LEGEND

- GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE (HIDDEN)
- NEW CONCRETE PAVEMENT
- NEW DECOMPOSE GRANITE
- NEW ASPHALT PAVEMENT
- NEW 80mm IMPERVIOUS CONCRETE PAVERS, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR & FINISH
- DIRECTION OF SURFACE FLOW. SURFACE FLOW SHALL SLOPE WAY FROM BUILDING AND SITE WALLS.
- LIMITS OF PRECISE GRADING PERMIT

GENERAL NOTES

1. ALL RETAINING WALLS TO BE CONSTRUCTED PER SEPARATE PLAN AND SEPARATE PERMIT.
2. ALL OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED PER SEPARATE PLANS AND SEPARATE PERMITS (SHOWN FOR REFERENCE ONLY).

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED ON-SITE SIDEWALK GRADES, INLETS & SWALES TO MATCH ST. IMPRV. PLANS; ADDED DECOMPOSED GRANITE SURFACE ALONG SOUTHERLY PATH; ADJ. FTP WALLS AND INLET LOCATIONS AS RESULT OF BLDG. FOOTING CHANGES; REVISED PROJECT ADDRESS; ADDED CONSTRUCTION NOTES; ADJ. SHEET # DUE TO ADDITION OF NEW DRIVEWAY	
2	1/16/15	REVISED TRANSFORMER AREA LAYOUT, ELEVATIONS & DRAINAGE	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Exp. 6/30/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **PRECISE GRADING DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-14**

R:\WORK\Laguna Niguel\C27\Precise Grading\MODELS\PG-14-P30.dwg May 11, 2015 - 12:15pm Jose



GRADING DETAIL - SOUTH EAST SIDE OF BUILDING

1

CONSTRUCTION NOTES

(3) CONSTRUCT 4-INCH THICK PCC SIDEWALK WITH #4 REBAR AT 18-INCH O.C. SEE SHEET C-4, DETAILS 4 & 5. SEE LANDSCAPE ARCHITECT'S PLANS FOR COLOR AND FINISH.

(9) CONSTRUCT 8-INCH CMU BLOCK FLOW THROUGH PLANTER SYSTEM, SEE LANDSCAPE ARCHITECT'S PLANS FOR COLORS AND FINISHES, SEE SHEETS C-20, C-21 & C-22. SLOPE EXTERIOR SURFACE AWAY FROM WALLS.

(12) CONSTRUCT PCC STAIRS AND HANDRAILS. SEE SHEET C-4, DETAIL 11.

(21) CONSTRUCT 2.5-FOOT WIDE STABILIZED EARTHEN SWALE. SEE SHEET C-4, DETAIL 13.

LEGEND:

GRADED SWALE TO BE SLOPED AT 1.0% MIN. TO DRAINAGE INLET. CROSS SLOPE FROM BUILDING TO BE 2.0% MIN. DOWN TO EARTHEN SWALE

NEW CONCRETE PAVEMENT

LIMITS OF PRECISE GRADING PERMIT

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED FTP WALL AND AREA DRAIN LOCATION TO AVOID CONFLICT WITH	
		BLDG. FOOTING; REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO	
		ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration 12/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION:
PRECISE GRADING DETAILS

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER
5376001

SHEET NO.
C-15 △

S:\ACAD\PLANS\Laguna Niguel\CAD\Precise Grading\MC5UA-PG-15-PGD.dwg May 11, 2015 - 12:16pm Jose





ENLARGED DETAIL
SCALE: 1=4'

STORM DRAIN NOTES

(30) PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(31) PROVIDE AND INSTALL 6-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(32) PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(36) PROVIDE AND INSTALL PVC STORM DRAIN CLEANOUT. SEE SHEET C-22, DETAILS 4 OR 8.

(37) PROVIDE AND INSTALL 9-INCH x 9-INCH LOW PROFILE ADAPTER (NDS #830) USE 9-INCH SQUARE GRATE IN GRASS AREA (NDS #990 "GREEN"). USE 9-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #881 "BLACK"). SEE SHEET C-22, DETAIL 10.

(38) PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

(39) PROVIDE AND INSTALL 6-INCH ROUND ATRIUM GRATE (NDS #90) IN SOIL AREAS AND 6-INCH ROUND GRATE (NDS #50) IN GRASS AREAS. SEE SHEET C-22, DETAIL 10.

(43) PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(45) PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

(46) REMOVE CONFLICTING PORTION OF THE EXISTING 10-INCH STORM DRAIN LINE, CONNECT PROPOSED STORM DRAIN LINE AS REQUIRED.

(50) PROVIDE STENCILING AT CATCH BASIN AND INLETS TO DISCOURAGE ILLEGAL DUMPING OF POLLUTANTS, SEE SHEET 22, DETAIL 7.

(51) PROVIDE AND INSTALL 4-INCH ROUND ADA COMPLIANT CHROME GRATE WITH PVC COLLAR (NDS #917SC).

(57) PROVIDE AND INSTALL 18-INCH x 18-INCH LOW PROFILE ADAPTER (NDS #1830) USE 18-INCH SQUARE GRATE IN GRASS AREA (NDS #1812 "GREEN"). USE 18-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1881 "BLACK"). SEE SHEET C-22, DETAIL 10.

(60) CONSTRUCT CURBSIDE GRATING CATCH BASIN PER S.P.P.W.C. STANDARD PLAN NO. 303-3. CONSTRUCT 8-INCH THICK PCC LOCAL DEPRESSION, SEE SHEET C-23, DETAIL 8 OR 10.

(61) CONSTRUCT CURB OPENING CATCH BASIN PER S.P.P.W.C. STANDARD PLAN NO. 300-3. CONSTRUCT 8-INCH THICK PCC LOCAL DEPRESSION, SEE SHEET C-23, DETAIL 9 OR 10.

(62) INSTALL 8-INCH DIAMETER NYLOPLAST DRAINAGE BASIN WITH ATRIUM GRATE. SEE SHEET C-5, DETAIL 1.

STORM DRAIN DEMO NOTES

[1] CUT & CAP EXISTING PVC STORM DRAIN LINE.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.

SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED LOCATIONS OR ADDED STORM DRAIN LINES & INLETS; SHEET WAS ADDED TO SHOW NEW DRIVEWAY.	
2	1/16/15	REVISED LOCATIONS OR ADDED STORM DRAIN LINES & INLETS AROUND TRANSFORMER ENCLOSURE	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 03/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠1
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER: 5376001

SHEET NO.: C-16 ⚠1

©KHR ARCHITECTS



STORM DRAIN NOTES

30 PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

31 PROVIDE AND INSTALL 6-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

32 PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

37 PROVIDE AND INSTALL 9-INCH x 9-INCH LOW PROFILE ADAPTER (NDS #930) USE 9-INCH SQUARE GRATE IN GRASS AREA (NDS #990 "GREEN"). USE 9-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #981 "BLACK"). SEE SHEET C-22, DETAIL 10.

38 PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

41 PROVIDE AND INSTALL ECCENTRIC REDUCER, SIZE PER PLAN.

43 PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

45 PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

46 REMOVE CONFLICTING PORTION OF THE EXISTING 10-INCH STORM DRAIN LINE, CONNECT PROPOSED STORM DRAIN LINE AS REQUIRED.

50 PROVIDE STENCILING AT CATCH BASIN AND INLETS TO DISCOURAGE ILLEGAL DUMPING OF POLLUTANTS, SEE SHEET 22, DETAIL 7.

57 PROVIDE AND INSTALL 18-INCH x 18-INCH LOW PROFILE ADAPTER (NDS #1830) USE 18-INCH SQUARE GRATE IN GRASS AREA (NDS #1812 "GREEN"). USE 18-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1881 "BLACK"). SEE SHEET C-22, DETAIL 10.

△1 60 CONSTRUCT CURBSIDE GRATING CATCH BASIN PER S.P.P.W.C. STANDARD PLAN NO. 303-3. CONSTRUCT 8-INCH THICK PCC LOCAL DEPRESSION, SEE SHEET C-23, DETAIL 8 OR 10. △2

STORM DRAIN DEMO NOTES

1 CUT & CAP EXISTING PVC STORM DRAIN LINE.

2 REMOVE EXISTING STORM DRAIN RISER.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.

SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED LOCATIONS OR ADDED STORM DRAIN LINES & INLETS; SHEET WAS	
		ADDED TO SHOW NEW DRIVEWAY.	
2	1/16/15	REVISED CATCH BASING TYPE, ADDED CNST. NOTE 60; STORM DRAIN LINES	
		& INLETS	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD △1
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-17** △1

K:\JOBS\JOB01\Copper Ridge\DGN\Precise Grading\PGBkmPG-11-7.dgn May 11, 2015 - 12:22pm jose



STORM DRAIN NOTES

(30) PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(31) PROVIDE AND INSTALL 6-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(32) PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(33) PROVIDE AND INSTALL 10-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(37) PROVIDE AND INSTALL 9-INCH x 9-INCH LOW PROFILE ADAPTER (NDS #930) USE 9-INCH SQUARE GRATE IN GRASS AREA (NDS #990 "GREEN"). USE 9-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #981 "BLACK"). SEE SHEET C-22, DETAIL 10.

(38) PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

(39) PROVIDE AND INSTALL 6-INCH ROUND ATRIUM GRATE (NDS #90) IN SOIL AREAS AND 6-INCH ROUND GRATE (NDS #50) IN GRASS AREAS. SEE SHEET C-22, DETAIL 10.

(41) PROVIDE AND INSTALL ECCENTRIC REDUCER, SIZE PER PLAN.

(43) PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(44) PROVIDE AND INSTALL 30° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(45) PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

(47) PROVIDE AND INSTALL 4'x8' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.

(54) CONSTRUCT 6-INCH WIDE ACO TRENCH DRAIN MODEL KS100S (K010 NEUTRAL CHANNEL DEPTH=6.96") ADA COMPLIENT GRATE AND H-20 LOADING, SEE SHEET C-22, DETAIL 12.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.

N

0 5 10 20 30
SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS: SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 6/30/15 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-18

N:\PROJECTS\5376001 Crown Cabot\DWG\Precise Grading\5376001-Pre-18-SD.dwg May 11, 2015 - 12:24pm

STORM DRAIN NOTES

(30) PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(33) PROVIDE AND INSTALL 10-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(36) PROVIDE AND INSTALL PVC STORM DRAIN CLEANOUT. SEE SHEET C-22, DETAILS 4 OR 8.

(38) PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"), USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

(43) PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(45) PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

(46) REMOVE CONFLICTING PORTION OF THE EXISTING 10-INCH STORM DRAIN LINE, CONNECT PROPOSED STORM DRAIN LINE AS REQUIRED.

(48) PROVIDE AND INSTALL 8'x12' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.

(51) PROVIDE AND INSTALL 4-INCH ROUND ADA COMPLIANT CHROME GRATE WITH PVC COLLAR (NDS #917SC).

(52) CONNECT TO EXIST STORM DRAIN PIPE. CUT-IN A WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL, SEE SHEET C-23 DETAIL 4.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.



STORM DRAIN DETAIL
SCALE: 1"=4'



811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	RAISED INLET AND OUTLET ELEVATION OF FTP, ADDED INLETS & STORM PIPING; REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Exp. 12/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-19 ⚠**

©\\KHR1\Projects\Projects\5376001\Phase 3\Engineering\Working\5376-19-SD.dwg May 11, 2015 - 12:28pm Jose



STORM DRAIN NOTES

(30) PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(32) PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(33) PROVIDE AND INSTALL 10-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(34) PROVIDE AND INSTALL 12-INCH HDPE DRAINAGE PIPE. SEE SHEET C-22, DETAIL 2 FOR PIPE BEDDING.

(35) PROVIDE AND INSTALL 18-INCH HDPE DRAINAGE PIPE. SEE SHEET C-22, DETAIL 2 FOR PIPE BEDDING.

(36) PROVIDE AND INSTALL PVC STORM DRAIN CLEANOUT. SEE SHEET C-22, DETAILS 4 OR 8.

(37) PROVIDE AND INSTALL 9-INCH x 9-INCH LOW PROFILE ADAPTER (NDS #930) USE 9-INCH SQUARE GRATE IN GRASS AREA (NDS #990 "GREEN"). USE 9-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #981 "BLACK"). SEE SHEET C-22, DETAIL 10.

(38) PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

(39) PROVIDE AND INSTALL 6-INCH ROUND ATRIUM GRATE (NDS #90) IN SOIL AREAS AND 6-INCH ROUND GRATE (NDS #50) IN GRASS AREAS. SEE SHEET C-22, DETAIL 10.

(41) PROVIDE AND INSTALL ECCENTRIC REDUCER, SIZE PER PLAN.

(42) PROVIDE AND INSTALL HDPE WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL. SEE SHEET C-23, DETAIL 4.

(43) PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(45) PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

(47) PROVIDE AND INSTALL 4'x8' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.

(58) CONSTRUCT 4-INCH WIDE PRE-SLOPED ACO (KS100S) TRENCH DRAIN W/ ADA "HEEL RESISTANT" STAINLESS STEEL GRATE AND FRAME. SEE SHEET C-22, DETAIL 15.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.



ENLARGED DETAIL
SCALE: 1"=4'



CULVERT SECTION (TYPE B)-MODIFIED (FOR REFERENCE ONLY - SEE OFF-SITE IMPROVEMENT PLANS)
SCALE: 1"=4'

0 5 10 20 30
SCALE: 1"=10'

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS			
NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED BUILDING FOOTING DRAIN POCs; RELOCATED FILTERRA BOX AND	
		LOWERED INLET & OUTLET INVERTS; REDESIGNED SD INLETS AND PIPING PER	
		CHANGES TO OFF-SITE STREET IMPROVEMENT PLANS; REVISED PROJECT	
		ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expires: 03/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION:
STORM DRAIN PLAN

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA
PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-20

© M:\MGR\MGR1-Laguna Niguel\123\Precise Grading\MCSLN-PG-20-SD.dwg May 11, 2015 - 12:26pm Jose



STORM DRAIN NOTES

(30) PROVIDE AND INSTALL 4-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(32) PROVIDE AND INSTALL 8-INCH PVC (SDR 35) DRAINAGE PIPE. SEE SHEET C-22, DETAIL 3 FOR PIPE BEDDING.

(34) PROVIDE AND INSTALL 12-INCH HDPE DRAINAGE PIPE. SEE SHEET C-22, DETAIL 2 FOR PIPE BEDDING.

(36) PROVIDE AND INSTALL PVC STORM DRAIN CLEANOUT. SEE SHEET C-22, DETAILS 4 OR 8.

(38) PROVIDE AND INSTALL 12-INCH x 12-INCH LOW PROFILE ADAPTER (NDS #1230) USE 12-INCH SQUARE GRATE IN GRASS AREA (NDS #1212 "GREEN"). USE 12-INCH SQUARE ATRIUM GRATE IN SOIL AREAS (NDS #1290 "BLACK"). SEE SHEET C-22, DETAIL 10.

(39) PROVIDE AND INSTALL 6-INCH ROUND ATRIUM GRATE (NDS #90) IN SOIL AREAS AND 6-INCH ROUND GRATE (NDS #50) IN GRASS AREAS. SEE SHEET C-22, DETAIL 10.

(41) PROVIDE AND INSTALL ECCENTRIC REDUCER, SIZE PER PLAN.

(42) PROVIDE AND INSTALL HDPE WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL, SEE SHEET C-23, DETAIL 4.

(43) PROVIDE AND INSTALL 45° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(44) PROVIDE AND INSTALL 30° SMOOTH SWEEP RADIUS BEND (SIZE PER MAIN LINE). SEE SHEET C-22, DETAIL 16.

(45) PROVIDE AND INSTALL 45° WYE (SIZE PER MAIN LINES).

(48) PROVIDE AND INSTALL 8'x12' FILTERRA BIORETENTION ROOF DRAIN SYSTEM BY KRISTAR. SEE SHEET C-23, DETAIL 7 AND MANUFACTURER'S SPECIFICATIONS FOR ADDITIONAL INFORMATION.

(52) CONNECT TO EXIST STORM DRAIN PIPE. CUT-IN A WYE WITH NYLOPLAST DISSIMILAR PIPE MATERIAL ADAPTER ON LATERAL, SEE SHEET C-23 DETAIL 4.

(56) REMOVE EXISTING 8-INCH STORM DRAIN LINE AND RISER AT PIPE FITTING.

(59) CONSTRUCT 4-INCH WIDE PRE-SLOPED ACO (KS1005) TRENCH DRAIN, ADJACENT TO STAIRS, W/ ADA "HEEL RESISTANT" STAINLESS STEEL GRATE AND FRAME. SEE SHEET C-4, DETAIL 11.

GENERAL NOTES

1. ALL PIPE FITTINGS MUST BE SMOOTH SWEEP RADIUS FITTINGS.

N

0 5 10 20 30

SCALE: 1"=10'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED BUILDING FOOTING DRAIN POCs; RELOCATED FILTERRA BOX AND LOWERED INLET & OUTLET INVERTS; RELOCATED SD INLETS AND PIPING TO AVOID CONFLICTS WITH BLDG FOOTING; REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration: 6/30/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-21

K:\WORK\5376001-Laguna Niguel\CD\Precise Grading\MCBLK-PG-21-SD.dwg May 11, 2015 - 12:50pm Jose



ROUND LANDSCAPE AREA DRAIN (OFF-LINE)



ROUND LANDSCAPE AREA DRAIN (TERMINAL)



ROUND LANDSCAPE AREA DRAIN (IN-LINE)



SQUARE LANDSCAPE AREA DRAIN (OFF-LINE)



SQUARE LANDSCAPE AREA DRAIN (TERMINAL)



SQUARE LANDSCAPE AREA DRAIN (IN-LINE)



SUMP BOX LANDSCAPE AREA DRAIN



SUMP BOX PEDESTRIAN AREA DRAIN

SCALE: NONE

AREA DRAIN DETAILS | 10

HDPE STORM DRAIN PIPE - GENERIC SPECIFICATIONS

GENERAL NOTES:

CORRUGATED H.D.P.E. PIPE AND FITTINGS SHALL HAVE BELL AND SPIGOT JOINTS, SMOOTH INTERIOR COMPLYING WITH AASHTO DESIGNATION M-252(4"-10"), M-294(12"-36") TYPE S OR MP8-95 (42"&48") TYPE S OR D. THE PIPE AND FITTINGS SHALL BE MADE OF VIRGIN H.D.P.E. COMPOUNDS CONFORMING TO THE REQUIREMENTS OF CELL CLASSIFICATION 324420C. PIPE AND FITTINGS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D-2321 AND THE PROJECT SPECIFICATIONS. ALL PIPE SHALL BE ADVANCED WITH A REGULAR CORRUGATION TYPE OF RUBBER GASKETED JOINT. ALL FITTINGS SHALL UTILIZE RUBBER GASKETED JOINTS. ALL RUBBER GASKET SHALL MEET THE REQUIREMENTS OF ASTM F-477.

WHERE H.D.P.E. STORM DRAIN LINES ARE SHOWN ON A RADIUS, THE CONTRACTOR SHALL FURNISH ELBOWS OR SHORT LENGTHS, OR A COMBINATION OF BOTH. THE MAXIMUM ALLOWABLE ANGLE IS 45 DEGREES. THE MAXIMUM ALLOWABLE HORIZONTAL DEFLECTION AT A JOINT WITHOUT AN ELBOW IS 3 DEGREES.

SMOOTH INTERIOR TYPE S AND TYPE D HIGH DENSITY POLYETHYLENE PIPE SHALL BE ADS N-12 STORM DRAIN PIPE OR APPROVED EQUAL.

GENERAL NOTES:

NATIVE MATERIAL TO BE USED FOR BACKFILL IN THE PIPE TRENCH SHALL BE EXAMINED FOR SUITABILITY OF INTENDED USE BY THE GEOTECHNICAL CONSULTANT PRIOR TO ANY TRENCH BACKFILL. COMPACTION TEST FOR EACH LIFT SHALL BE OBTAINED AT THE DISCRETION OF THE ENGINEER. THE ENGINEER OR GEOTECHNICAL CONSULTANT SHALL DECIDE THE EXACT LOCATION AT WHICH THE COMPACTION TESTS ARE OBTAINED.

AT ALL TIMES PIPE MATERIALS SHALL BE HANDLED WITH CARE TO AVOID DAMAGE. WHETHER MOVED BY HAND, FORKLIFT, OR HOISTS, MATERIAL SHALL NOT BE DROPPED, BUMPED, OR ALLOWED TO IMPACT ON ITSELF. DOUBLE STRAPPING SHOULD BE USED WITH ALL LIFTS. WHENEVER POSSIBLE, IN DISTRIBUTING THE PIPE AT THE JOB SITE, IT SHALL BE UNLOADED ADJACENT TO OR NEAR THE LOCATION WHERE IT IS TO BE INSTALLED.

GENERAL BEDDING NOTES:

1. TRENCH WIDTH DETAIL AND BACKFILL REQUIREMENTS SHALL BE EXECUTED AT CONTRACTOR'S DISCRETION. BEDDINGS 'A' AND 'B' SHALL BE FROM PIPE SUBGRADE.
2. IF UNSTABLE SOIL IS ENCOUNTERED, GEOTECHNICAL ENGINEER WILL DETERMINE CONTRACTOR'S OPTIONS. BEDDINGS 'A', 'B' AND 'C' SHALL BE FROM PIPE SUBGRADE.
3. 2 SACK SLURRY CEMENT BACKFILL SHALL BE USED WHERE COVER IS 2-FEET AND UNDER.
4. NATIVE OR IMPORTED BACKFILL AT THE CONTRACTORS DISCRETION TO BE BROUGHT UP IN LIFTS AND COMPACTED TO 90%.



TRENCH WIDTH AND BACKFILL REQUIREMENTS:

BEDDING 'A'
NATURAL CLEAN SAND PER SSPWC 306-1.3 COMPACTED TO A RELATIVE COMPACTION OF NOT LESS THAN 90%.

PIPE DIAMETER	TRENCH WIDTH
18" TO 36"	O.D. + 36"
39" TO 48"	O.D. + 48"

BEDDING 'B'
SLURRY OR CLSM, 2 SACK CEMENT

PIPE DIAMETER	TRENCH WIDTH
18" TO 48"	O.D. + 10"



MANHOLE CONNECTION DETAILS

SCALE: NONE

HDPE TRENCHING AND BEDDING | 2



GENERAL NOTES:

* STRENGTH OF CONCRETE AND CEMENT TYPE FRO ALL CONCRETE IN CONTACT WITH SOIL TO BE DETERMINED BY THE PROJECT SOIL ENGINEER IN THE FIELD BASED ON SULFATE CONTENT OF THE SOIL.

SCALE: NONE

4" WIDE TRENCH DRAIN | 15



GENERAL NOTES:

* STRENGTH OF CONCRETE AND CEMENT TYPE FRO ALL CONCRETE IN CONTACT WITH SOIL TO BE DETERMINED BY THE PROJECT SOIL ENGINEER IN THE FIELD BASED ON SULFATE CONTENT OF THE SOIL.

SCALE: NONE

12" WIDE TRENCH DRAIN | 11



NOTES:

1. STENCIL OR SIGNAGE IS REQUIRED AT ALL DRAINAGE INLETS.
2. STORM DRAIN MESSAGE WILL BE APPLIED IN SUCH A WAY AS TO PROVIDE A CLEAR LEGIBLE IMAGE.
3. STORM DRAIN MESSAGE WILL BE PERMANENTLY APPLIED DURING THE CONSTRUCTION OF THE CURB AND GUTTER USING A METHOD APPROVED BY THE COUNTY.

SCALE: NONE

STORM DRAIN STENCILING | 7



SCALE: NONE

PVC TRENCHING AND BEDDING | 3



HDPE SMOOTH SWEEP RADIUS PIPE FITTINGS

PVC SMOOTH SWEEP RADIUS PIPE FITTINGS

SCALE: NONE

SMOOTH SWEEP RADIUS PIPE FITTINGS | 16



SCALE: NONE

6" WIDE TRENCH DRAIN ON STRUCTURAL DECK | 12



TERMINAL CLEANOUT | 8



SCALE: NONE

IN-LINE CLEANOUT | 4

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
#1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 12/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-22 ⚠

K:\JOBS\5376001-Laguna Niguel-CA\Planning\Exhibits\PCB-22-1203.dwg May 11, 2015 - 12:31pm rose



LOCAL DEPRESSION DETAIL #1 | 8



LOCAL DEPRESSION DETAIL #2 | 9



LOCAL DEPRESSION DETAIL #3 | 10

⚠

SIZING CHART - FOOTPRINT & PIPE SIZES

FILTERRA ROOFDRAIN UNIT SIZE OR (FTRD)	W DIMENSION (WIDTH)	L DIMENSION (LENGTH)	PERFORATED PIPE & CLEANOUT SIZE	TREE GRATE QUANTITY/SIZE	INLET/OUTLET PIPE SIZE (DIAMETER INCHES)
FTRD 4.0'x8.0'	4.00' [48.00"]	8.00' [96.00"]	4.00"	1 EA. / 3' x 3'	6.00" & 8.00"
FTRD 8.0'x12.0'	8.00' [96.00"]	12.00' [144.00"]	6.00"	2 EA. / 4' x 4'	6.00", 8.00" & 10.00"



CUTAWAY SECTION



PLAN VIEW

SCALE: NONE

TYPICAL FILTERRA ROOF DRAIN BOX | 7



PLAN VIEW



SECTION "A"–"A"



SECTION "B"–"B" ALTERNATIVE BOTTOM OUTLET

SCALE: NONE

24" x 24" PCC DROP INLET | 1



WYE/ADAPTER CONNECTION

SCALE: NONE

DISSIMILAR PIPE MATERIAL ADAPTERS | 4

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	ADDED DETAILS 8, 9 & 10; REVISED PROJECT ADDRESS; SHIFTED SHEET #	
		DUE TO ADDITION OF NEW DRIVEWAY	
2	1/16/15	REVISED DETAIL 10, LOCAL DEPRESSION #3	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration 03/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION: **STORM DRAIN DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-23** ⚠

H:\WORK\5376001-Laguna Niguel\CUT\Precise Grading\WORK-PG-23-C23.dwg May 11, 2015 - 12:33pm Jose



FLOW THROUGH PLANTER #1

SCALE: 1"=4'



SECTION (FTP #1)

SCALE: 1"=4'



FLOW THROUGH PLANTER #2

SCALE: 1"=4'



SECTION (FTP #2)

SCALE: 1"=4'



FLOW THROUGH PLANTER #3

SCALE: 1"=4'



SECTION (FTP #3)

SCALE: 1"=4'



⚠1 FLOW THROUGH PLANTER #4

SCALE: 1"=4'



⚠1 SECTION (FTP #4)

SCALE: 1"=4'



⚠1 FLOW THROUGH PLANTER #5

SCALE: 1"=4'



⚠1 SECTION (FTP #5)

SCALE: 1"=4'



FLOW THROUGH PLANTER #6

SCALE: 1"=4'



SECTION (FTP #6)

SCALE: 1"=4'

LEGEND:

1. 6" DIA. PERFORATED SCH. 40 PVC PIPE, PROVIDE END CAPS AT BOTH ENDS OF PIPE.
2. SLOPE CLOSED MESH REMOVABLE GRATE BOLTED TO SUPPORT FRAME
3. 6" DIA. SCH. 40 PVC CLEANOUT TO 12" ABOVE FINISH GRADE. PROVIDE SEALED CAP.
4. 3'-0" WIDE x 3'-6" LONG x 3" THICK CONC. SPLASH PAD AT ALL BUILDING DRAINS.
5. STEEL OR ALUMINUM CLEANOUT FRAME AND GRATE SYSTEM TO SUPPORT SURROUNDING SOILS, ENGINEERED BY OTHERS. SUBMIT SHOP DRAWINGS FOR CIVIL REVIEW.
6. 8" CMU PLANTER WALL & FOUNDATION UNDER SEPARATE PERMIT.
7. CORE DRILL CMU WALL 1-INCH THAN PROPOSED OUTLET PIPE DIA. AND FILL WITH NON-METALLIC NON-SHRINK GROUT.
8. WATERPROOFING SYSTEM WITHIN FLOW THROUGH PLANTERS SHALL BE DESIGNED BY THE OWNER'S WATERPROOFING CONSULTANT TO ENSURE A WATER TIGHT SYSTEM.
9. 6" DIA. SCH. 40 PVC CROSS FITTING.
10. 6" x 90° SCH. 40 PVC BEND.
11. ORIFICE DRILLED INTO OVERFLOW DRAIN WALL AT UNDERDRAIN PIPE INVERT
12. FORM A 1.5" DEEP x 1" + FRAME THICKNESS WIDE GROOVE IN CONCRETE AND PROVIDE A CONTINUOUS WATERTIGHT CONNECTION USING AN APPROVED SEALANT.
13. WATERTIGHT CONNECTION, INSTALL 1/8" TO 1/4" THICK x 2" WIDE CONTINUOUS 30 DUROMETER NEOPRENE GASKET, ALL AROUND VAULT FRAME.
14. BOLT FLANGE TO OVERFLOW DRAIN WALL

GENERAL OUTLET DETAIL NOTES:

1. GRATE SHALL BE MOUNTED USING STAINLESS STEEL HARDWARE AND PROVIDED WITH HINGED AND LOCKABLE OR BOLTABLE ACCESS PANELS.
2. GRATE SHALL BE STAINLESS STEEL, ALUMINUM OR STEEL. STEEL GRATES SHALL BE HOT DIP GALVANIZED AND MAY BE HOT POWDER PAINTED AFTER GALVANIZING.
3. GRATE SHALL BE DESIGNED SUCH THAT THE DIAGONAL DIMENSION OF EACH OPENING IS SMALLER THAN THE DIAMETER OF THE OUTLET PIPE.
4. STRUCTURAL DESIGN OF GRATE SHALL BE BASED ON FULL HYDROSTATIC HEAD WITH ZERO HEAD DOWNSTREAM OF GRATE.



GENERAL OUTLET DETAIL

SCALE: NONE



TYPICAL FLOW THROUGH PLANTER DETAIL (#1)

SCALE: NONE

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED FLOW THROUGH PLANTERS LOCATION AND/OR SIZE TO AVOID	
		CONFLICTS WITH BLDG. FOOTING; REVISED PROJECT ADDRESS; SHIFTED	
		SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION: **FLOW THROUGH PLANTER DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠1
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-24 ⚠1**

R:\MDR\MDR1-Laguna Niguel\C01\Precise Grading\MDR1-Pc-24-FTP2.dwg May 11, 2015 - 12:39pm dale



FLOW THROUGH PLANTER #7

SCALE: 1"=4'



FLOW THROUGH PLANTER #9

SCALE: 1"=4'



FLOW THROUGH PLANTER #11

SCALE: 1"=4'



SECTION (FTP #7)

SCALE: 1"=4'



SECTION (FTP #9)

SCALE: 1"=4'



SECTION (FTP #11)

SCALE: 1"=4'



FLOW THROUGH PLANTER #8

SCALE: 1"=4'



FLOW THROUGH PLANTER #10

SCALE: 1"=4'



FLOW THROUGH PLANTER #12

SCALE: 1"=4'



SECTION (FTP #8)

SCALE: 1"=4'



SECTION (FTP #10)

SCALE: 1"=4'



SECTION (FTP #12)

SCALE: 1"=4'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 03/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **FLOW THROUGH PLANTER DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-25** ⚠

K:\JOBS\5376001 Crown Niguel\CD\Precise Grading\5376DA-PG-25-FTP01.dwg May 11, 2015 - 12:38pm Jose



FLOW THROUGH PLANTER #13

SCALE: 1"=4'



SECTION (FTP #13)

SCALE: 1"=4'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Expiration 12/31/16 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION: **FLOW THROUGH PLANTER DETAILS**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD ⚠
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-26** ⚠

©\\KHR\HCR~1\Support Mgmt\CIV\Precise Grading\WORK\A-PG-26-FTP0.dwg May 11, 2015 - 12:41pm JOHN



SEGMENT DATA

SEGMENT	BEARING OR Δ	RADIUS	LENGTH
1	N12°26'40"W	–	3.34'
2	N12°26'40"W	–	1.94'
3	N12°26'40"W	–	3.00'
4	N46°31'37"E	–	6.32'
5	N77°33'20"E	–	10.18'
6	N12°26'40"W	–	6.15'
7	N77°33'20"E	–	7.00'
8	N77°33'20"E	–	3.17'
9	43°47'51"	10.00'	7.64'
10	06°57'29"	47.00'	5.71'
11	143°09'38"	1.50'	3.75'
12	N77°33'20"E	–	11.54'
13	90°00'00"	3.00'	4.71'
14	N12°26'40"W	–	5.17'
15	90°00'00"	1.00'	1.57'
16	11°48'58"	43.51'	8.97'
17	68°52'10"	1.00'	1.20'
18	N04°46'08"W	–	0.17'
19	90°11'54"	1.00'	1.57'
20	91°06'48"	1.00'	1.59'
21	N05°19'31"E	–	0.16'
22	67°45'33"	1.00'	1.18'
23	03°01'27"	285.00'	15.04'
24	08°46'34"	290.00'	44.42'
25	11°48'58"	43.51'	8.97'
26	105°00'00"	5.00'	9.16'
27	15°00'00"	12.00'	3.14'
28	N27°26'40"	–	2.23'
29	N77°33'20"E	–	4.00'
30	N77°33'20"E	–	8.83'
31	N77°33'20"E	–	2.57'
32	N77°33'20"E	–	2.74'
33	N77°33'20"E	–	16.47'
34	N77°33'20"E	–	1.50'
35	N12°26'40"W	–	2.87'
36	N77°33'20"E	–	16.92'
37	N12°26'40"W	–	8.50'
38	N12°26'40"W	–	28.40'
39	36°52'12"	17.00'	10.44'
40	17°45'10"	49.00'	10.44'
41	17°45'10"	35.00'	10.85'
42	17°45'10"	25.00'	7.75'
43	17°45'10"	59.00'	18.28'
44	N20°26'40"W	–	4.04'
45	N77°33'20"E	–	32.00'
46	N12°26'40"W	–	9.98'



DETAIL "A"
SCALE: 1"=5'



DETAIL "B"
SCALE: 1"=5'



DETAIL "C"
SCALE: 1"=10'



DETAIL "D"
SCALE: 1"=8'

GENERAL NOTES

1. THIS SHEET IS NOT PART OF THE GRADING PERMIT (SHOWN FOR REFERENCE ONLY).

0 10 20 40 60
SCALE: 1"=20'

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES, THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/11/14	REVISED PROJECT ADDRESS. SHIFTED SHEET # DUE TO THE ADDITION OF NEW DRIVEWAY; ADDED CURB DATA INFORMATION FOR THE NEW DRIVEWAY & TRANSFORMER ENCLOSURE.	
2	1/16/15	REVISED TRANSFORMER AREA; REVISED ALIGNMENT OF ROADWAY; ADDED CURB DATA INFORMATION; ADDED DETAILS C & D	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration: 03/31/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION:
HORIZONTAL CONTROL PLAN

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA
PERMIT # G13-005

PROJECT NUMBER
5376001

SHEET NO.
C-27

E:\WORTK\WORK-Laguna Niguel\CUV\Precise Grading\WORK-NG-27-HRZT.dwg May 11, 2015 - 12:43pm Jose

RESIDENT ENTRANCE SIGN DETAIL

SCALE: NONE



FIRE LANE ENTRANCE SIGN DETAIL

SCALE: NONE



FIRE LANE STRIPING DETAIL

SCALE: NONE

SPEED TABLE PROFILE DETAIL

SCALE: NONE



"V" SHAPED MARKING DETAIL

SCALE: NONE



STRIPING NOTES

70. PAINT TOP AND CURB FACE RED WITH 4-INCH HIGH WHITE LETTERS LABELED "NO PARKING FIRE LANE" AT 30-FEET O.C.
71. PAINT 12-INCH WIDE WHITE LIMIT LINE AND STOP LEGEND PER CALTRANS STANDARD PLAN NO. A24D AND A24E.
72. PAINT 4-INCH DOUBLE YELLOW CENTERLINE PER CALTRANS STANDARD PLAN NO. A20A, DETAIL 21.
73. PAINT 8-INCH SOLID RED STRIPING AND 3-INCH HIGH WHITE LETTERS LABELED "NO PARKING FIRE LANE" AT CENTER OF THE 8-INCH RED STRIPING. SEE DETAIL ON THIS SHEET.
74. PAINT 8-INCH SINGLE POCKET CHANNELIZATION LINE.
75. PAINT 4-INCH SINGLE YELLOW CENTERLINE, PER CALTRANS STANDARD PLAN NO.A20A.
76. PAINT SOLID WHITE THERMOPLASTIC DIRECTION OF TRAVEL ARROWS.
77. PAINT WHITE THERMOPLASTIC TURN LANE ARROWS, PER CALTRANS STANDARD PLAN NO. A24A, TYPE IV.
78. PAINT WHITE THERMOPLASTIC TURN LANE ARROWS, PER CALTRANS STANDARD PLAN NO. A24A, TYPE VII.
79. PAINT SOLID WHITE "V" SHAPED MARKINGS CENTERED IN EACH TRAVEL LANE. SEE DETAIL ON THIS SHEET.

SIGNING NOTES

80. PROVIDE AND INSTALL NEW ACCESSIBILITY SITE WARNING SIGN ON A SQUARE GALVANIZED STEEL POST. SEE DETAIL ON THIS SHEET.
81. PROVIDE AND INSTALL NEW FIRE LANE ENTRANCE SIGN ON A SQUARE GALVANIZED STEEL POST. SEE DETAIL ON THIS SHEET.
82. PROVIDE AND INSTALL "RESIDENT ENTRANCE ONLY NO GUEST ACCESS" SIGN ON A SQUARE GALVANIZED STEEL POST. SEE DETAIL ON THIS SHEET.
83. PROVIDE AND INSTALL R1-1 (STOP) SIGN PER MUTCD STANDARDS.
84. CONSTRUCT ASPHALT CONCRETE SPEED TABLE. SEE DETAIL ON THIS SHEET.

GENERAL NOTES

1. THIS SHEET IS NOT PART OF THE GRADING PERMIT (SHOWN FOR REFERENCE ONLY).
2. ALL STRIPING SHALL BE APPLIED WITH MINIMUM TWO COATS OF PAINT.



TYPICAL SITE WARNING SIGN DETAIL

SCALE: NONE



TYPICAL SIGNAGE POST DETAIL

SCALE: NONE



811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW	
		DRIVEWAY; RENUMBERED & ADD CONSTRUCTION NOTES; ADDED ENTRANCE	
		AND FIRE LANE STRIPING	
2	3/25/15	CHANGED ROADWAY ALIGNMENT; ADDED RESIDENT ENTRANCE AND STOP SIGNS;	
		ADDED SPEED TABLE; ADDED DETAILS; ADD CONSTRUCTION NOTES	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER — JAMES H. KAWAMURA — No. 30560 — Expiration 03/19/16 — CIVIL — STATE OF CALIFORNIA

SHEET DESCRIPTION: **SIGNING AND STRIPING PLAN**

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER **5376001**

SHEET NO. **C-28**

G:\KHR\WORK\Laguna Niguel\CDI\Precise Grading\WORK\A-Pln-28-SS.dwg May 11, 2015 - 12:40pm Jose



CONSTRUCTION NOTES

1. INSTALL 6-FOOT HIGH CHAIN LINK FENCE WITH SCREENING AROUND PERIMETER OF PROPERTY.
2. BMP'S SE-1, SE-5, SE-6, SE-12: PLACE SILT FENCE AND GRAVEL BAGS (3 HIGH) ALONG CONSTRUCTION PERIMETER IN ACCORDANCE WITH CASQA BMP STANDARD.
3. STOCKPILE BMPs THROUGHOUT CONSTRUCTION AREA FOR REPLACEMENT OF DAMAGED BMP'S AND/OR CREATION OF EMERGENCY BMPs.
4. BMP TC-1: CONSTRUCT TEMPORARY DRIVE PAD WITH A WIDTH EQUAL TO THE ENTRANCE/EXIT OF PROJECT SITE AND AT LEAST 50-FEET MIN. IN LENGTH. PURPOSE OF DRIVE PAD IS TO MITIGATE TRACKING OF MUD AND SILT ONTO PUBLIC STREETS. DESIGN ACCORDING TO CASQA STANDARD.
5. BMP WM-9: PLACE PORTABLE TOILET 50-FEET AWAY FROM DOWNSTREAM DRAINAGE FACILITIES, WATERCOURSES, AND CONSTRUCTION PERIMETER. SECONDARY CONTAINMENT SHALL BE RPOVIDED IN CASE OF SPILLS. USE CASQA BMP STANDARD.
6. BMP SE-7: SWEEP AND/OR VACUUM ALL STREETS AND SIDEWALKS, AS NEEDED, TO REMOVE VISIBLE SEDIMENT TRACKED FROM THE CONSTRUCTION SITE. ANY TRACKED SEDIMENT WILL BE REMOVED PRIOR TO THE END OF THE WORK DAY. USE CASQA BMP STANDARD.
7. BMP WM-5: PLACE WATERTIGHT TRASH CONTAINERS AWAY FROM DRAINAGE FACILITIES AND WATERCOURSES. ARRANGEMENTS FOR WASTE COLLECTION SHALL BE MADE PRIOR TO TWO-THIRDS CAPACITY. TRASH CONTAINERS SHALL BE COVERED AT THE END OF WORK DAY. USE CASQA BMP STANDARD.
8. BMP SE-4, SE-6: PLACE CHECK DAM AT INTERVALS BASED ON GRADES AS SPECIFIED BY DETAIL ON SHEET 29.
9. BMP SE-5: PLACE FIBER ROLLS OR STRAW WATTLES ALONG EVEN CONTOURS AT VERTICAL SPACING SPECIFIED BY DETAIL ON SHEET 29.
11. SPRAY EARTHGUARD OR EQUIVALENT ON ALL ACTIVE AND NON-ACTIVE SOIL AREAS THROUGHOUT THE ENTIRE SITE. APPLICATION SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S STANDARDS AND REAPPLIED AS NEEDED.
12. SE-10: PLACE GRAVEL BAGS AND FILTER FABRIC AT CATCH BASINS TO PROVIDE FOR DESILTING OF RAIN OR EXCESS WATER. USE CASQA BMP STANDARD.
13. BMP'S WM-1, WM-3, WM-5, WM-7, WM-8: USE PRIMARY (COVER) AND SECONDARY (GRAVEL BAG BERM) CONTAINMENT FOR TEMPORARY EXPOSED STORAGE AREAS IN ACCORDANCE WITH CASQA BMP STANDARDS.
14. BMP'S WM-8, NS-8: LOCATE TEMPORARY CONCRETE TRUCK/EQUIPMENT WASHOUT AREA AT LEAST 50-FEET FROM DOWNSTREAM STORM DRAIN INLETS. TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD NOT ALLOW FOR ANY RUNOFF AND SHALL HAVE SUFFICIENT CAPACITY TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS. WASHOUTS SHALL HAVE SECONDARY CONTAINMENT. USE CASQA BMP STANDARD.

LEGEND

- PERIMETER CONTROL (SILT FENCE, GRAVEL BAGS, ETC.)
- DIRECTION OF PROPOSED SURFACE DRAINAGE
- CONSTRUCTION NOTE CALLOUT REFERENCE
- RIGHT OF WAY LINE/PROPERTY LINE
- CONSTRUCTION FENCE
- GRAVEL BED AND/OR (IF ON ASPHALT)) RUMBLE PLATES
- TEMPORARY DUMPSTER AREA
- TEMPORARY PORTABLE TOILET
- GRAVEL BAG
- FIBER ROLL/STRAW WATTLE
- TEMPORARY STORAGE AREA
- TEMPORARY CONCRETE WASHOUT AREA

NOTE

SPRAY EARTHGUARD OR EQUIVALENT ON ALL DISTURBED AREAS, DISTURBED SLOPES AND STOCKPILES, PRIOR TO THE RAIN EVENT/STORM (SEE NOTE BELOW).

50. DURING THE WET SEASON, BETWEEN OCTOBER 1ST AND APRIL 30TH, EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEEDS 40%. DURING THE REMAINDER OF THE YEAR, THE EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE ONSITE AND READY FOR INSTALLATION WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEED 50% AND IN PLACE AT THE END OF EACH DAY WHEN THE 48 HOUR PROBABILITY-OF-RAIN EXCEEDS 50%.

BMP - NOISE CONTROL

BEST MANAGEMENT PRACTICES, NOISE CONTROL (GSP MM4.10-1 – MM4.10-4) – PRIOR TO ISSUANCE OF GRADING OR BUILDING PERMITS, THE PROJECT APPLICANT SHALL DOCUMENT ON THE GRADING AND BUILDING PLANS THE FOLLOWING CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPS), TO BE IMPLEMENTED BY CONTRACTORS TO REDUCE CONSTRUCTION NOISE LEVELS:

(MM4.10-1)

a. ENSURE THAT CONSTRUCTION EQUIPMENT IS PROPERLY MUFFLED ACCORDING TO INDUSTRY STANDARDS AND IN GOOD WORKING CONDITION.

b. PLACE NOISE-GENERATING CONSTRUCTION EQUIPMENT AND LOCATE CONSTRUCTION STAGING AREAS AWAY FROM SENSITIVE USES, WHERE FEASIBLE.

c. SCHEDULE HIGH NOISE-PRODUCING ACTIVITIES BETWEEN THE HOURS OF 8:00 AM AND 5:00 PM TO MINIMIZE DISRUPTION ON SENSITIVE USES, MONDAY THROUGH SATURDAY.

d. IMPLEMENT NOISE ATTENUATION MEASURES, WHICH MAY INCLUDE, BUT ARE NOT LIMITED TO, TEMPORARY NOISE BARRIERS OR NOISE BLANKETS AROUND STATIONARY CONSTRUCTION NOISE SOURCES, WHERE FEASIBLE.

e. USE ELECTRIC AIR COMPRESSORS AND SIMILAR POWER TOOLS RATHER THAN DIESEL EQUIPMENT, WHERE FEASIBLE.

f. CONSTRUCTION-RELATED EQUIPMENT, INCLUDING HEAVY-DUTY EQUIPMENT, MOTOR VEHICLES, AND PORTABLE EQUIPMENT, SHALL BE TURNED OFF WHEN NOT IN USE FOR MORE THAN 10 MINUTES.

g. CONSTRUCTION HOURS, ALLOWABLE WORKDAYS, AND THE PHONE NUMBER OF THE JOB SUPERINTENDENT SHALL BE CLEARLY POSTED AT ALL CONSTRUCTION ENTRANCES TO ALLOW FOR SURROUNDING OWNERS AND RESIDENTS TO CONTACT THE JOB SUPERINTENDENT. IF THE CITY OR THE JOB SUPERINTENDENT RECEIVES A COMPLAINT, THE SUPERINTENDENT SHALL INVESTIGATE, TAKE APPROPRIATE CORRECTIVE ACTION, AND REPORT THE ACTION TAKEN TO THE REPORTING PARTY.

h. (MM4.10-2) CONSTRUCTION STAGING AREAS ALONG WITH THE OPERATION OF EARTHMOVING EQUIPMENT WITHIN THE PROJECT AREA WOULD BE LOCATED AS FAR AWAY FROM VIBRATION AND NOISE SENSITIVE SITES AS POSSIBLE.

i. (MM4.10-3) HEAVILY LOADED TRUCKS USED DURING CONSTRUCTION WOULD BE ROUTED AWAY FROM RESIDENTIAL STREETS.

j. (MM4.10-4) USE OF NOISE-REDUCING PILE DRIVING TECHNIQUES IF NEARBY STRUCTURES ARE SUBJECT TO PILE DRIVING NOISE AND VIBRATION. THESE TECHNIQUES INCLUDE PRE-DRILLING PILE HOLES (IF FEASIBLE, BASED ON SOILS) TO THE MAXIMUM FEASIBLE DEPTH, INSTALLING STATE-OF-THE-ART INTAKE AND EXHAUST MUFFLERS ON PILE DRIVING EQUIPMENT, VIBRATING PILES INTO PLACE WHEN FEASIBLE, AND INSTALLING SHROUDS AROUND THE PILE DRIVING HAMMER WHERE FEASIBLE. PILE DRIVING ACTIVITIES SHALL BE SCHEDULED BETWEEN THE HOURS OF 8:00 AM AND 4:00 PM ON MONDAYS THROUGH FRIDAYS ONLY.

BMP - AIR QUALITY

BEST MANAGEMENT PRACTICES, AIR QUALITY (GSP MM4.2-1 – MM4.2-14) – PRIOR TO ISSUANCE OF A GRADING AND/OR A BUILDING PERMIT, THE FOLLOWING BMPS SHALL BE INCLUDED ON THE PROJECT GRADING AND/OR BUILDING PLANS, AS DETERMINED APPROPRIATE BY THE COMMUNITY DEVELOPMENT DIRECTOR OR BUILDING OFFICIAL:

a. (MM4.2-1) NAME AND PHONE NUMBER OF THE CONTRACTOR'S SUPERINTENDENT HIRED BY THE APPLICANT SHALL BE SUBMITTED TO THE COMMUNITY DEVELOPMENT AND PUBLIC WORKS DEPARTMENTS. IN ADDITION, CLEARLY VISIBLE SIGNS SHALL BE POSTED ON THE PERIMETER OF THE SITE INDICATING WHO SHALL BE CONTACTED FOR INFORMATION REGARDING THIS DEVELOPMENT AND ANY ONSTRUCTION/GRADING-RELATED CONCERNS. THIS CONTACT PERSON SHALL BE AVAILABLE IMMEDIATELY TO ADDRESS ANY CONCERNS OR ISSUES RAISED BY ADJACENT PROPERTY OWNERS DURING THE CONSTRUCTION ACTIVITY. S/HE WILL BE RESPONSIBLE FOR ENSURING COMPLIANCE WITH THE CONDITIONS HEREIN, SPECIFICALLY, GRADING ACTIVITIES, TRUCK ROUTES, CONSTRUCTION HOURS, NOISE, ETC. SIGNS SHALL INCLUDE THE APPLICANT'S CONTACT NUMBER REGARDING GRADING AND CONSTRUCTION ACTIVITIES, AND "1-800-CUTSMOG" IN THE EVENT THERE ARE CONCERNS REGARDING FUGITIVE DUST AND COMPLIANCE WITH SCAQMD RULE NO. 403.

b. (MM4.2-2) WIND BARRIERS SHALL BE INSTALLED ALONG THE PERIMETER OF THE SITE AND/OR AROUND AREAS BEING GRADED.

c. (MM4.2-3) PROJECT APPLICANT SHALL ESTABLISH AN ON-SITE CONSTRUCTION EQUIPMENT STAGING AREA AND CONSTRUCTION WORKER PARKING, LOCATED ON EITHER PAVED SURFACES OR UNPAVED SURFACES SUBJECTED TO SOIL STABILIZATION TREATMENTS, AS CLOSE AS POSSIBLE TO A PUBLIC ROADWAY.

d. (MM4.2-4) PROJECT APPLICANT SHALL CONTROL ACCESS TO THE PUBLIC BY LIMITING CURB CUTS/DRIVEWAYS TO MINIMIZE PROJECT CONSTRUCTION IMPACTS UPON ROADWAY TRAFFIC OPERATIONS.

e. (MM4.2-5) PROJECT APPLICANT SHALL PROPERLY MAINTAIN NONVEHICULAR EQUIPMENT ENGINES TO MINIMIZE THE VOLUME OF EXHAUST EMISSIONS.

f. (MM4.2-6) PROJECT APPLICANT SHALL USE ELECTRICITY FROM POWER POLES, RATHER THAN TEMPORARY DIESEL OR GASOLINE POWERED GENERATORS, AS FEASIBLE.

g. (MM4.2-7) PROJECT APPLICANT SHALL USE ON-SITE MOBILE EQUIPMENT POWERED BY ALTERNATIVE FUEL SOURCES (I.E., METHANOL, NATURAL GAS, PROPANE, OR BUTANE) AS FEASIBLE.

h. (MM4.2-8) PROJECT APPLICANT SHALL PAVE ALL CONSTRUCTION ROADS AS FEASIBLE.

i. (MM4.2-9) PROJECT APPLICANT SHALL PROVIDE RIDESHARING OR SHUTTLE SERVICE FOR CONSTRUCTION WORKERS, AS FEASIBLE.

BMP - AIR QUALITY (CONTINUED)

j. (MM4.2-10) PROJECT APPLICANT SHALL PROVIDE TEMPORARY TRAFFIC CONTROLS SUCH AS A FLAG PERSON, DURING ALL PHASES OF CONSTRUCTION TO MAINTAIN SMOOTH TRAFFIC FLOW, AS DEEMED NECESSARY BY THE PUBLIC WORKS DIRECTOR.

k. (MM4.2-11) PROJECT APPLICANT SHALL PROVIDE DEDICATED TURN LANES FOR MOVEMENT OF CONSTRUCTION TRUCKS AND EQUIPMENT ON AND OFF SITE, AS DEEMED NECESSARY BY THE PUBLIC WORKS DIRECTOR.

l. (MM4.2-12) PROJECT APPLICANT SHALL REROUTE CONSTRUCTION TRUCKS AWAY FROM CONGESTED STREETS OR SENSITIVE RECEPTOR AREAS, AS FEASIBLE;

m. (MM4.2-13) PROJECT APPLICANT SHALL REQUIRE THE USE OF CLEANEST BURNING DIESEL HAUL TRUCKS AVAILABLE, SUCH AS TRUCKS THAT MEET 2010 MODEL YEAR EPA STANDARDS.

n. (MM4.2-14) PROJECT APPLICANT SHALL ENSURE THAT ALL ARCHITECTURAL COATING (PAINT AND PRIMER) PRODUCTS APPLIED DURING CONSTRUCTION HAVE A LOW TO NO VOC RATING.

BMP - DUST CONTROL

DUST CONTROL – DURING CLEARING, GRADING, EARTH-MOVING, OR EXCAVATION OPERATIONS, EXCESSIVE FUGITIVE DUST EMISSIONS SHALL BE CONTROLLED BY REGULAR WATERING OR OTHER DUST-PREVENTIVE MEASURES USING THE FOLLOWING PROCEDURES, AS SPECIFIED IN THE SCAQMD RULE 403 LISTED BELOW. PRIOR TO GRADING PERMIT ISSUANCE, THESE CONTROL TECHNIQUES SHALL BE NOTED ON THE PROJECT GRADING PLANS. COMPLIANCE WITH THE MEASURE SHALL BE SUBJECT TO PERIODIC SITE INSPECTIONS BY THE CITY.

a. ON-SITE VEHICLE SPEED SHALL BE LIMITED TO 15 MILES PER HOUR.

b. ALL MATERIAL EXCAVATED OR GRADED SHALL BE SUFFICIENTLY WATERED TO PREVENT EXCESSIVE AMOUNTS OF DUST. WATERING SHALL OCCUR AT LEAST TWICE DAILY WITH COMPLETE COVERAGE, PREFERABLY IN THE LATE MORNING AND AFTER WORK IS DONE FOR THE DAY.

c. STREETS ADJACENT TO THE PROJECT SITE SHALL BE SWEPT AS NEEDED TO REMOVE SILT THAT MAY HAVE ACCUMULATED FROM CONSTRUCTION ACTIVITIES SO AS TO PREVENT EXCESSIVE AMOUNTS OF DUST.

d. ALL TRUCKS HAULING DIRT, SAND, SOIL, OR OTHER LOOSE MATERIALS SHALL BE SECURELY COVERED, OR MAINTAIN AT LEAST 0.6 METERS (2 FEET) OF FREEBOARD (VERTICAL SPACE BETWEEN THE TOP OF THE LOAD AND TOP OF THE TRAILER) IN ACCORDANCE WITH THE REQUIREMENTS OF CALIFORNIA VEHICLE CODE (CVC) SECTION 23114.

e. THE AREA DISTURBED BY CLEARING, GRADING, EARTH-MOVING, OR EXCAVATION OPERATIONS SHALL BE MINIMIZED SO AS TO PREVENT EXCESSIVE AMOUNTS OF DUST.

f. VISIBLE DUST BEYOND THE PROPERTY LINE EMANATING FROM THE PROJECT SHALL BE PREVENTED TO THE MAXIMUM EXTENT FEASIBLE.

BEST MANAGEMENT PRACTICES

THE FOLLOWING BMPs AS OUTLINED IN, BUT NOT LIMITED TO, THE CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA) CONSTRUCTION BEST MANAGEMENT PRACTICES (BMP) HANDBOOK, NOVEMBER 2009, OR LATEST REVISED EDITION, MAY APPLY DURING THE CONSTRUCTION OF THIS PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED IF DEEMED APPROPRIATE BY THE PROJECT ENGINEER OR THE BUILDING OFFICIAL).

TEMPORARY EROSION CONTROL

EC-1	SCHEDULING
EC-2	PRESERVATION OF EXISTING VEGETATION
EC-3	HYDRAULIC MULCH
EC-4	HYDROSEEDING
EC-5	SOIL BINDERS
EC-6	STRAW MULCH
EC-7	GEOTEXTILES AND MATS
EC-8	WOOD MULCHING
EC-9	EARTH DIKES AND DRAINAGE SWALES
EC-10	VELOCITY DISSIPATION DEVICES
EC-11	SLOPE DRAINS
EC-12	STREAMBANK STABILIZATION
EC-13	RESERVED (FORMERLY PAM)
EC-14	COMPOST BLANKETS
EC-15	SOIL PREPARATION/ROUGHENING
EC-16	NON-VEGETATIVE STABILIZATION

TEMPORARY SEDIMENT CONTROL

SE-1	SILT FENCE
SE-2	SEDIMENT BASIN
SE-3	SEDIMENT TRAP
SE-4	CHECK DAM
SE-5	FIBER ROLLS
SE-6	GRAVEL BAG BERM
SE-7	STREET SWEEPING AND VACUUMING
SE-8	SANDBAG BARRIER
SE-9	STRAW BALE BARRIER
SE-10	STORM DRAIN INLET PROTECTION
SE-11	ACTIVE TREATMENT SYSTEMS
SE-12	TEMPORARY SILT DIKE
SE-13	*COMPOST SOCKS AND BERMS*
SE-14	BIOFILTER BAGS

WIND EROSION CONTROL

WE-1	WIND EROSION CONTROL

EQUIPMENT TRACKING CONTROL

TC-1	STABILIZED CONSTRUCTION ENTRANCE/EXIT
TC-2	STABILIZED CONSTRUCTION ROADWAY
TC-3	ENTRANCE/OUTLET TIRE WASH

NON-STORMWATER MANAGEMENT CONTROL

NS-1	WATER CONSERVATION PRACTICES
NS-2	DEWATERING OPERATIONS
NS-3	PAVING AND GRINDING OPERATIONS
NS-4	TEMPORARY STREAM CROSSING
NS-5	CLEAR WATER DIVERSION
NS-6	ILLICIT CONNECTION/DISCHARGE
NS-7	POTABLE WATER/IRRIGATION
NS-8	VEHICLE AND EQUIPMENT CLEANING
NS-9	VEHICLE AND EQUIPMENT FUELING
NS-10	VEHICLE AND EQUIPMENT MAINTENANCE
NS-11	PILE DRIVING OPERATIONS
NS-12	CONCRETE CURING
NS-13	CONCRETE FINISHING
NS-14	MATERIAL OVER WATER
NS-15	DEMOLITION ADJACENT TO WATER
NS-16	TEMPORARY BATCH PLANTS

WASTE MANAGEMENT & MATERIALS POLLUTION CONTROL

WM-1	MATERIAL DELIVERY AND STORAGE
WM-2	MATERIAL USE
WM-3	STOCKPILE MANAGEMENT
WM-4	SPILL PREVENTION AND CONTROL
WM-5	SOLID WASTE MANAGEMENT
WM-6	HAZARDOUS WASTE MANAGEMENT
WM-7	CONTAMINATED SOIL MANAGEMENT
WM-8	CONCRETE WASTE MANAGEMENT
WM-9	SANITARY/SEPTIC WASTE MANAGEMENT
WM-10	LIQUID WASTE MANAGEMENT

N

0 10 20 40 60

SCALE: 1"=20'

811 Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION:

EROSION CONTROL PLAN - PRECISE GRADING

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA

PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-29

R:\PROJ\MCR1-crown Niguel\CU\Precise Grading\MCR1A-PG-29-30-EC.dwg May 11, 2015 - 12:48pm nate

MATCHLINE SEE SHEET C-29



CONSTRUCTION NOTES

1. INSTALL 6-FOOT HIGH CHAIN LINK FENCE WITH SCREENING AROUND PERIMETER OF PROPERTY.
2. BMP'S SE-1, SE-5, SE-6, SE-12: PLACE SILT FENCE AND GRAVEL BAGS (3 HIGH) ALONG CONSTRUCTION PERIMETER IN ACCORDANCE WITH CASQA BMP STANDARD.
3. STOCKPILE BMPs THROUGHOUT CONSTRUCTION AREA FOR REPLACEMENT OF DAMAGED BMP'S AND/OR CREATION OF EMERGENCY BMPs.
6. BMP SE-7: SWEEP AND/OR VACUUM ALL STREETS AND SIDEWALKS, AS NEEDED, TO REMOVE VISIBLE SEDIMENT TRACKED FROM THE CONSTRUCTION SITE. ANY TRACKED SEDIMENT WILL BE REMOVED PRIOR TO THE END OF THE WORK DAY. USE CASQA BMP STANDARD.
7. BMP WM-5: PLACE WATERTIGHT TRASH CONTAINERS AWAY FROM DRAINAGE FACILITIES AND WATERCOURSES. ARRANGEMENTS FOR WASTE COLLECTION SHALL BE MADE PRIOR TO TWO-THIRDS CAPACITY. TRASH CONTAINERS SHALL BE COVERED AT THE END OF WORK DAY. USE CASQA BMP STANDARD.
8. BMP SE-4, SE-6: PLACE CHECK DAM AT INTERVALS BASED ON GRADES AS SPECIFIED BY DETAIL ON THIS SHEET.
9. BMP SE-5: PLACE FIBER ROLLS OR STRAW WATTLES ALONG EVEN CONTOURS AT VERTICAL SPACING SPECIFIED BY DETAIL ON THIS SHEET.
11. SPRAY EARTHGUARD OR EQUIVALENT ON ALL ACTIVE AND NON-ACTIVE SOIL AREAS THROUGHOUT THE ENTIRE SITE. APPLICATION SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S STANDARDS AND REAPPLIED AS NEEDED.
12. SE-10: PLACE GRAVEL BAGS AND FILTER FABRIC AT CATCH BASINS TO PROVIDE FOR DESILTING OF RAIN OR EXCESS WATER. USE CASQA BMP STANDARD.
13. BMP'S WM-1, WM-3, WM-5, WM-7, WM-8: USE PRIMARY (COVER) AND SECONDARY (GRAVEL BAG BERM) CONTAINMENT FOR TEMPORARY EXPOSED STORAGE AREAS IN ACCORDANCE WITH CASQA BMP STANDARDS.
14. BMP'S WM-8, NS-8: LOCATE TEMPORARY CONCRETE TRUCK/EQUIPMENT WASHOUT AREA AT LEAST 50-FEET FROM DOWNSTREAM STORM DRAIN INLETS. TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD NOT ALLOW FOR ANY RUNOFF AND SHALL HAVE SUFFICIENT CAPACITY TO CONTAIN ALL LIQUID AND CONCRETE WASTE GENERATED BY WASHOUT OPERATIONS. WASHOUTS SHALL HAVE SECONDARY CONTAINMENT. USE CASQA BMP STANDARD.

LEGEND

- PERIMETER CONTROL (SILT FENCE, GRAVEL BAGS, ETC.)
- DIRECTION OF PROPOSED SURFACE DRAINAGE
- CONSTRUCTION NOTE CALLOUT REFERENCE
- RIGHT OF WAY LINE/PROPERTY LINE
- CONSTRUCTION FENCE
- GRAVEL BED AND/OR (IF ON ASPHALT)) RUMBLE PLATES
- TEMPORARY DUMPSTER AREA
- TEMPORARY PORTABLE TOILET
- GRAVEL BAG
- FIBER ROLL/STRAW WATTLE
- TEMPORARY STORAGE AREA
- TEMPORARY CONCRETE WASHOUT AREA

NOTE

SPRAY EARTHGUARD OR EQUIVALENT ON ALL DISTURBED AREAS, DISTURBED SLOPES AND STOCKPILES, PRIOR TO THE RAIN EVENT/STORM (SEE NOTE BELOW).

50. DURING THE WET SEASON, BETWEEN OCTOBER 1ST AND APRIL 30TH, EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEEDS 40%. DURING THE REMAINDER OF THE YEAR, THE EROSION CONTROL PROTECTIVE DEVICES AND MEASURES SHALL BE ONSITE AND READY FOR INSTALLATION WHEN THE 5-DAY PROBABILITY-OF-RAIN EXCEED 50% AND IN PLACE AT THE END OF EACH DAY WHEN THE 48 HOUR PROBABILITY-OF-RAIN EXCEEDS 50%.



SE-1: SILT FENCE
SCALE: NONE



SE-6: GRAVEL BAGS ALONG CONSTRUCTION AREA
SCALE: NONE



SE-5: FIBER ROLLS
SCALE: NONE



SE-4: GRAVEL BAG CHECK DAM
SCALE: NONE





TC-1 TRACKING CONTROL
SCALE: NONE



GRAVEL BAG STOCKPILE
SCALE: NONE



SE-10: INLET PROTECTION FOR RAIN EVENTS
SCALE: NONE



SE-10 STORM DRAIN INLET PROTECTION
SCALE: NONE

0 10 20 40
SCALE:1=20

Know what's below. Call before you dig.

NOTICE TO CONTRACTOR

CONTRACTOR HEREBY AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING THE SAFETY OF PERSONS AND PROPERTIES; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD HARMLESS THE OWNER AND ENGINEER FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR ENGINEER.

REVISIONS

NO.	DATE:	DESCRIPTION	APPROVAL
1	12/12/14	REVISED PROJECT ADDRESS; SHIFTED SHEET # DUE TO ADDITION OF NEW DRIVEWAY.	

PREPARED BY:
KHR ASSOCIATES
CONSULTING ENGINEERS/SURVEYORS/PLANNERS
4100 Newport Place Drive - Suite 200
Newport Beach, California 92660
(949) 756-6440 Fax (949) 756-6444
UNDER THE SUPERVISION OF: JAMES H. KAWAMURA (R.C.E. 30560)

REGISTERED PROFESSIONAL ENGINEER JAMES H. KAWAMURA No. 30560 Exp. 12/31/15 CIVIL STATE OF CALIFORNIA

SHEET DESCRIPTION:
EROSION CONTROL PLAN - PRECISE GRADING

CROWN CABOT LUXURY APARTMENTS
27960 CABOT ROAD
LAGUNA NIGUEL, CALIFORNIA
PERMIT # G13-005

PROJECT NUMBER 5376001

SHEET NO. C-30

R:\MGMT\MGMT-Laguna Niguel\GD\Precise Grading\MGMTpc-29-30-GD.dwg May 11, 2015 - 12:47pm JOSE

REVISION

PERMIT # G13-05

FEE RECEIPT #

THE CITY OF LAGUNA NIGUEL
REGULATION
GRADING SECTION
APPROVED

This set of plans & specifications must be kept on the job at all times and it is unlawful to make any changes or alterations on same without written permission by the Grading Section, City of Laguna Niguel.
This stamping of this plan & specifications SHALL NOT be held to permit or be an approval of the violation of any provisions of any City and County Ordinance or State Law.
This permit is an application for inspection the issuance of which is not an approval or an authorization for the work specified herein.
This permit does not authorize on permit, nor shall it be construed as authorizing or permitting the violation or failure to comply with an applicable law. The City of Laguna Niguel, its boards, departments, officers and employees, hereby expressly deny any warranty or responsibility for the design, construction or operation of this work described, the condition of the property or the soil upon which the work is undertaken. No statement by any officer, employee, or agent written or oral, can alter this denial.
This grading plan does not Allow or Approve ANY Construction within the dedicated Right of Way. A permit is required from Department of Public Works for encroachment on public Right of Way

Gary Hoeben
BUILDING OFFICIAL

GRADING PERMIT # G13-05

☐ PRELIMINARY
NO BUILDING PERMITS SHALL BE ISSUED UNTIL THIS PERMIT IS SUPERSEDED BY A PRECISE GRADING PERMIT

☑ PRECISE
BUILDING PERMITS MAY BE ISSUED AFTER ROUGH GRADING HAS BEEN APPROVED

By _____

Date 5/14/15